

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Intermountain Refining Co., Inc.

Address: PO Box 35, Farmington, NM 87499

Phone: (505) 326-2668 Operator License #: 32356

Type of Well: Gas DH KCCPR Rec 2/3 Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 10/29/2008 (Date)

by: Ken Jehlic (Observed) (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

Chase Depth to Top: 2742 Bottom: 2762 T.D. 2952  
\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

API Number: 15-171-20660-0000

Lease Name: Mildred Strobe

Well Number: #1A

Spot Location (QQQQ): NE - NE - SW - NE  
1376 Feet from  North /  South Section Line

1376 Feet from  East /  West Section Line

Sec. 28 Twp. 18 S. R. 31  East  West

County: Scott

Date Well Completed: 07/12/2007

Plugging Commenced: 11/21/2008

Plugging Completed: 11/21/2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		0	363	7"	363	0
		0	2927	4-1/2"	2927	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

165 sacks cement (60/40 Poz. 4%gel) and 150# hulls pumped down 4/12" production casing. Pressured to 1,000PSI.

15 sacks cement (60/40 Poz. 4%gel) pumped down 7" surface casing behind production casing. Pressured to 500PSI.

Cutoff surface and production casing 5' below surface level and backfilled with existing dirt.

RECEIVED  
KANSAS CORPORATION COMMISSION

Name of Plugging Contractor: SwiftServices, Inc. License #: 32382

Address: N Hwy 283, Ness City, KS 67560

DEC 01 2008

Name of Party Responsible for Plugging Fees: Intermountain Refining Co., Inc.

CONSERVATION DIVISION  
WICHITA, KS

State of New Mexico County, San Juan, ss.

Rick L Hurt (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Rick L Hurt

(Address) PO Box 35, Farmington NM 87499

SUBSCRIBED and SWORN TO before me this 25th day of November 20 08

Notary Public My Commission Expires: Jan 6 2012

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202