

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 039-00590-00-01 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 4/8/52

Well Operator: VESS OIL CORPORATION KCC License #: 5030
(Owner / Company Name) (Operator's)

Address: 1700 Waterfront Parkway, Bldg City: Wichita

State: KS Zip Code: 67206 Contact Phone: (316) 682 - 1537 X103

Lease: Adell NW Well #: 7W Sec. 35 Twp. 5 S. R. 27 East West

SW - NW - NW Spot Location / QQQQ County: Decatur

4320 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

5039 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # 15,099 Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8-5/8 Set at: 279 Cemented with: 200 Sacks

Production Casing Size: 5-1/2 Set at: 3907 Cemented with: 200 Sacks

List (ALL) Perforations and Bridgeplug Sets: LKC (3649-3773) Perf'd and sqzd @ 2800' w/200 sx; 1450' w/425 sx; 900' w/300 sx; braden head w/100 sx

Elevation: 2657 (G.L. / K.B.) T.D.: 3908 PBTD: 3803 Anhydrite Depth: 2240
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): In accordance with KCC rules and regulations

RECEIVED
KANSAS CORPORATION COMMISSION

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? NA

DEC 11 2008

CONSERVATION DIVISION
WICHITA, KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Brett Hildebrand

Phone: (785) 871 - 7311

Address: 1104 Nixon Drive City / State: Norton, KS

Plugging Contractor: Allied Cementing Co., Inc. KCC License #: _____
(Company Name) (Contractor's)

Address: P.O. Box 31, Russell, KS 67665-0031 Phone: (785) 483 - 2627

Proposed Date and Hour of Plugging (if known?): January 2009

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 12/8/08 Authorized Operator / Agent: [Signature]
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Dist # 4
[Handwritten initials]

BARNETT DRILLING, INC.
LOG OF MARY A. TAYLOR WELL NO. 1
SW $\frac{1}{4}$ NW $\frac{1}{4}$ NW $\frac{1}{4}$ SECTION 35-5S-27W.
DECATUR COUNTY, KANSAS

DATE COMMENCED: April 8, 1952.

DATE COMPLETED: April 19, 1952.


Formation	From	To	Remarks
Clay and Sand	0	40	
Sand	40	60	
Shale and Shells	60	225	
Sand	225	255	
Shale and Shells	255	279	Set 8 5/8" Surface Pipe @ 279 feet; Cemented with 200 sacks.
Shale and Shells	279	1100	
Sand	1100	1300	
Shale	1300	1350	
Shale and Shells	1350	1750	
Lime	1750	1787	
Shale and Shells	1787	2240	
Anhydrite	2240	2277	
Shale	2277	2420	
Shale and Lime	2420	2685	
Lime	2685	2753	
Lime and Shale	2753	2990	
Lime	2990	3037	
Lime and Shale	3037	3170	
Lime	3170	3195	
Shale and Lime	3195	3260	
Lime	3260	3605	
Lime and Shale	3605	3660	
Lime	3660	3910	
Total Depth		3910	

RECEIVED
KANSAS CORPORATION COMMISSION
DEC 11 2008
CONSERVATION DIVISION
WICHITA, KS

2740
2659
2240
419

Certificate.

I, F. R. Stubblefield, of Barnett Drilling, Inc., hereby certify that to the best of my knowledge and belief, the above is a true and correct log of the Mary A. Taylor Well No. 1, located SW $\frac{1}{4}$ NW $\frac{1}{4}$ NW $\frac{1}{4}$ of Section 35-5S-27W, Decatur County, Kansas.



Subscribed and sworn to before me, in and for the County of Sedgwick, State of Kansas, this 24th day of April, 1952.


_____ Notary Public

My commission expires February 27, 1956.



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

VESS OIL CORPORATION
1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206-6619

December 15, 2008

Re: N W ADELL #7W
API 15-039-00590-00-01
35-5S-27W, 4320 FSL 5039 FEL
DECATUR COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after June 13, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550