

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-083-20911-00-00  
Spot: SENESEW Sec/Twnshp/Rge: 5-24S-21W  
1697 feet from S Section Line, 3138 feet from E Section Line  
Lease Name: VIRGINIA GLEASON Well #: 5  
County: HODGEMAN Total Vertical Depth: 4641 feet

Operator License No.: 8914  
Op Name: H & C OIL OPERATING INC.  
Address: PO BOX 86  
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		650		150.83
CIBP		2700		WITH 2 SX CMT
CIBP		4380		OPEN HOLE COMPLETION
PROD 4.5		4639	0	WITH 125 SX CMT
SURF 8.625		605		WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/05/2005 11:45 AM  
Plug Co. License No.: 33645 Plug Co. Name: H2 PLAINS, LLC  
Proposal Rcvd. from: CHARLES R. RAMSAY Company: H & C OIL OPERATING Phone: (785) 434-7434

Proposed Plugging Method: BRIDGE PLUG @ 2700'. BRIDGE PLUG @ 650'. PERFORATE @ 630' RUN TBG TO 630' CIRCULATE CMT ON BOTH SIDES.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/05/2008 12:55 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

TOP OF FISH @ 2700'. JUNK IN HOLE. CIBP @ 2700' WITH 2 SX CMT. CIBP @ 650' WITH 2 SX CMT. PERFORATE @ 630'. RUN TBG TO 630' & PUMP 165 SX CMT TO SURFACE BOTH SIDES.

Perfs:


**INVOICED**  
DATE 12-16-08  
INV. NO. 2009060841

RECEIVED  
KANSAS CORPORATION COMMISSION  
**NOV 19 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed

Jerry W. Stapleton  
(TECHNICIAN)  
PIRT II