

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

KCC ~~PKT~~ GPS 4918 4950

API Well Number: 15-065-01847-00-01
Spot: NWNWNE Sec/Twnshp/Rge: 6-10S-23W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: HOFF NW LKC Well #: 202W
County: GRAHAM Total Vertical Depth: 3973 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4029	0	w/125 sxs cmt
SURF	8.625	210	0	w/150 sxs cmt

129.12

Well Type: EOR UIC Docket No: E16528.5 Date/Time to Plug: 11/05/2008 1:30 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls.
DV Tool at 2077' w/540 sxs cwc.

Plugging Proposal Received By: PAT BEDORE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/05/2008 3:20 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2300' - pumped 150 sxs 60/40 pozmix - 4% gel with 100# hulls.
Pulled tubing to 740' - pumped 150 sxs 60/40 pozmix - 4% gel with 300# hulls to circulate to surface.
Pulled all tubing - pumped 25 sxs 60/40 pozmix - 4% gel to fill 5 1/2" casing.
8 5/8" pressured to 500# immediately.

Perfs:

INVOICED
DATE 12-16-08
INV. NO. 2009060847

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 19 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #43957.

Plugged through: TBG

District: 04

Signed Pat Bedore
(TECHNICIAN)

CM

Form CP-2/3

PKT

NOV 14 2008

6-10-23W
NW NW NE

C-G DRLG & N APPLEMAN #2 JOHNSON


Contr. C-G DRLG GRAHAM County

E 2453 RB Comm. Comp. 5-26-61 IP 50 BOPD/LANS KC

Tops	Depth	Datum
ANH	2063	+390
TOP	3544	-1091
HEFB	3760	-1307
TQR	3783	-1330
LANS	3796	-1343
TD	4030	-1577

Casing
8" 210
5" 4029

DST 3937-60/1 HR, 1800' G, 960' GSY O,
BHP 540-505/30"
DST 3964-75/30", 10' M, BHP 0/
PERF 8/3961-63: 8/3982-84: ACID 500: 28
BWPB & SSO: PLUG 3955: PERF 16/3944-48:
1 1/2 BO, MW: ACID 2500: SWB 25 B LO & SH G:
SQZ: REPERF 16/3944-48: ACID 500: SWB
5 1/2 BFPB, 20 1/2 WTR



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS