

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04409-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 9-16S-14W
2970 feet from S Section Line, 2310 feet from E Section Line
Lease Name: NUSS Well #: 1
County: BARTON Total Vertical Depth: 3430 feet

Operator License No.: 3273
Op Name: LOEB, HERMAN L.
Address: PO BOX 524
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3425	0	w/unknown sxs cmt
SURF	8.625	209	0	w/150 sxs cmt

\$111.35

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/19/2005 8:00 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: CL COX Company: LOEB, HERMAN L. Phone: (620) 786-2009

Proposed Plugging Method: Ordered 280 sxs cement and 500# hulls.
Casing leak - full of holes.

RECEIVED
KANSAS CORPORATION COMMISSION

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/20/2005 12:00 PM KCC Agent: ROGER MOSES

DEC 17 2008

Actual Plugging Report:

Perfs:

CONSERVATION DIVISION
WICHITA, KS

Ran tubing to 700' (top of fish) and circulated with 180 sxs cement with 500# hulls. TOC at 200'.
Pulled all tubing - tied to annulus and squeezed with 70 sxs cement.
Max. P.S.I. 100#. S.I.P. 100#.
Ordered 70 sxs more cement - pumped down 5 1/2" casing until ran out.
Checked cement top - still at 200' from surface.
Shut down for night - very muddy.
01-20-2005 - Topped well off with 35 sxs cement - casing remained full.
Well plugged.
Total of 355 sxs 60/40 pozmix - 10% gel and 500# hulls.

INVOICED
DATE 1-28-05
INV. NO. 2005061124

Remarks: ALLIED CEMENTING COMPANY. PAUL'S OILFIELD SERVICE-WATER.

Plugged through: TBG

District: 04

Signed

Roger Moses / af
(TECHNICIAN)

Form CP-2/3

JAN 25 2005

PCT

STERLING DRILLING

#1 NUSS

9-16-14W
SW SW NE

Contr. GROUP EXPL.

BARTON

County


E 1936 RB Comm. 6/12 62

Comp. 9/13/62

IP 45 BOPD, NW/LANS
3298-3336

LOG Tops	Depth	Datum
TOP	2851	- 915
JIEEB	3085	-1149
TOR	3104	-1168
LANS	3154	-1218
ARB	3413	-1477
LTD	3426	-1490
RTD	3430	-1494

Casing
 8" 209/150 sx:
 5" 3425:
 DST 3160-3218/1 HR, 458 V SL 0 &
 GCM, BHP 1047-365/ 30", FP
 49-56#:
 DST 3295-3375/90", 915' GIP,
 90' OCM, 60' H OCM, 60' MCO,
 360' MDY 0, 600' 0, BHP 1006-
 707/30", FP 55-430:
 NUSS S PERF 3298-3301; 32/
 3308-16; 16/3324-27; 8/
 3334-36; SG & 1/2 BOPH,
 NATL: ACID 3000: TST 92.
 24 80/3 HRS:



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS