

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-00777-00-00  
Spot: SWSESE Sec/Twnshp/Rge: 13-30S-8W  
330 feet from S Section Line, 990 feet from E Section Line  
Lease Name: TJADEN A Well #: 1  
County: KINGMAN Total Vertical Depth: 4350 feet

Operator License No.: 5363  
Op Name: BEREXCO, INC.  
Address: PO BOX 20380  
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1086		
PROD	5.5	4348		175 SX
SURF	8.625	199		160 SX

141.38

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/24/2008 8:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK 50' ABOVE PERFS. AND 5 SKS REC PIPE. 35 SKS 1300', 35 850', CIRC 250-0'.

Plugging Proposal Received By: DAVE WERTZ Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/24/2008 10:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A 35SKS OF CMT AND 50 LBS OF HULLS ON BOTTOM THRU TUBING. BOTTOM PLUG TAGGED AT 3820', PERFORATED AT 1300', 850', AND 250'. RAN TUBING TO 1280', AND SPOTTED 50 SKS OF CMT. PULLED TUBING TO 850', SPOTTED 50 SKS CMT. PULLED TUBING TO 250' AND CIRC CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3899	3904		

**INVOICED**  
DATE 12-19-08  
INV. NO. 2009060858


RECEIVED  
KANSAS CORPORATION COMMISSION  
NOV 26 2008  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING 60/40 4% GEL

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

  
(TECHNICIAN)

PKS