

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21823-00-00
Spot: SWNWNSW Sec/Twnshp/Rge: 14-30S-8W
2090 feet from S Section Line, 1470 feet from W Section Line
Lease Name: DOCKSTADER Well #: 5
County: KINGMAN Total Vertical Depth: 4218 feet

Operator License No.: 8740
Op Name: BRAMWELL PETROLEUM, INC.
Address: 15183 SW 25TH AVE
SPIVEY, KS 67142

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP	4.5	4165		
PROD	4.5	4217	2615	250 SX
SURF	8.625	209		150 SX

137.09

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/30/2008 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK TO 4100', CAP WITH 4 SKS CMT. 35 SKS 1150, 35 SKS 800, CIRC CMT 260-0

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 10/30/2008 10:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4100', AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 2615' AND PULLED TO 1150', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 800', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 260', WHERE CMT WAS CIRCD TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4170	4180		

INVOICED
DATE 12-19-08
INV. NO. 2009060859

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 26 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING 40/60 4% GEL

Plugged through: CSG

District: 02

Signed _____



(TECHNICIAN)

PVT