

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

KCC PKT Pen  
GPS

API Well Number: 15-051-25829-00-00

Spot: NESENWSW

Sec/Twnshp/Rge: 16-14S-16W

1832 1800 feet from S Section Line, 1030 feet from W Section Line

Lease Name: HUSER

4406 Well #: 1

County: ELLIS

Total Vertical Depth: 3500 feet

Operator License No.: 9067

Op Name: DAMAR RESOURCES, INC.

Address: 234 W 11TH STE A PO BOX 70  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3499	2563	w/145 sxs cmt
SURF	8.625	219	0	w/150 sxs cmt <u>113.75</u>

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 10/31/2008 10:30 AM

Plug Co. License No.: 6426

Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC

Proposal Rcvd. from: TOM

Company: DAMAR RESOURCES, INC.

Phone: (785) 625-0020

Proposed Plugging Method: Ordered 310 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Pull 2563' of 5 1/2".

Plugging Proposal Received By: BRUCE BASYE

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 10/31/2008 1:30 PM

KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Dropped 1 1/2 yards of sand to 3160'.  
Bail dumped 5 sxs cement on top of the sand.  
Cut 5 1/2" at 2563' - pumped 190 sxs cement with 400# hulls.  
Pulled 5 1/2" to 1140' - pumped 25 sxs cement and 2 BBL'S water.  
Pulled 5 1/2" to 421' - pumped 45 sxs cement - circulated.  
Pulled all 5 1/2" out of hole - hole full.

**INVOICED**

DATE 12-19-08  
INV. NO. 2009060861

RECEIVED  
KANSAS CORPORATION COMMISSION

**NOV 20 2008**

CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY CEMENTING COMPANY-TICKET #2270.

Plugged through: CSG

District: 04

Signed

(TECHNICIAN)

CM

Form CP-2/3

NOV 18 2008