

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22581-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 5-14S-22W
980 feet from S Section Line, 2180 feet from E Section Line
Lease Name: LYND FAMILY TRUST Well #: 1-5
County: TREGO Total Vertical Depth: 4350 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 372
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	235		

141.38

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/16/2008 3:30 AM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DOWNING-NELSON OIL CO INC. Phone: (785) 628-3449

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: NONE
Date/Time Plugging Completed: 10/16/2008 5:45 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug at 1800' w/25 sxs.
2nd. Plug at 875' w/100 sxs.
3rd. Plug at 285' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Perfs:

INVOICED
DATE 12-19-08
INV. NO. 2009060863

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 20 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Richard Williams
(TECHNICIAN)

CM PPT