

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-22522-00-00  
Spot: NWNESWSE Sec/Twnshp/Rge: 31-19S-10W  
1170 feet from S Section Line, 1800 feet from E Section Line  
Lease Name: BAYER Well #: 2  
County: RICE Total Vertical Depth: 3313 feet

Operator License No.: 30380  
Op Name: HUPFER OPERATING, INC.  
Address: PO BOX 216  
HAYS, KS 67601

| String | Size  | Depth (ft) | Pulled (ft) | Comment                   |
|--------|-------|------------|-------------|---------------------------|
| PROD   | 5.5   | 3305       | 2222        | 150 SX CMT.               |
| SURF   | 8.625 | 266        |             | 225 SX CMT. <u>107.67</u> |
| T1     | 2.875 | 3291       |             |                           |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/17/2008 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (620) 938-2943

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/17/2008 11:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SAND PERFS TO 3140' AND CAP WITH 5 SX'S CEMENT, SET CIBP @ 3000' AND CAP WITH 2 SX'S CEMENT. CUT OFF CASING @ 2222' AND PULL TO 1300' AND PUMP 35 SX'S CEMENT, PULL CASING TO 900' AND PUMP 35 SX'S CEMENT, PULL CASING TO 315' AND CIRCULATE CEMENT TO SURFACE.

Perfs:

| Top  | Bot  | Thru | Comments      |
|------|------|------|---------------|
| 3305 | 3313 |      | ARBUCKLE OPEN |
| 3198 | 3204 |      | LANSING       |
| 3047 | 3050 |      | LANSING       |

**INVOICED**

DATE 12-19-08

INV. NO. 2009060866

RECEIVED  
KANSAS CORPORATION COMMISSION

NOV 26 2008

CONSERVATION DIVISION  
WICHITA, KS

Remarks: 60-40 POZ, 4% GEL. COPELAND CEMENT TICKET #C-34255. LOG TECH TICKET #5529. USED 200 SX'S TOTAL.

Plugged through: CSG

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

PKT