

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21897-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 7-28S-5W
388 feet from S Section Line, 4837 feet from E Section Line
Lease Name: HILGER Well #: 1-7
County: KINGMAN Total Vertical Depth: 3950 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 S MARKET ST
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3949	2850	175 SXS CMT
SURF	8.625	280		190 SXS CMT 28.38
T1	2.375	3768		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/10/2008 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK 3770', CAP WITH 5 SKS OF CMT. RECOVER CASING. 35 SKS 550', CIRC CMT FROM 330-0'

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 10/10/2008 2:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND FROM 3886' TO 3770', AND CAPPED WITH 5 SKS OF CMT. THE CASING WAS RECOVERED FROM 2850', AND PULLED TO 550', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 330', WHERE CMT WAS CIRC TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3822	3830		

INVOICED
DATE 12-19-08
INV. NO. 2009060867

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 26 2008
CONSERVATION DIVISION
WICHITA KS

Remarks: QUALITY OIL WELL CEMENTING 60/40 4% GEL

Plugged through: CSG

District: 02

Signed [Signature]
(TECHNICIAN)

PKT