

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-03704-00-01
Spot: NENENW Sec/Twnshp/Rge: 14-10S-19W
330 feet from N Section Line, 2310 feet from W Section Line
Lease Name: PELTON Well #: B-1
County: ROOKS Total Vertical Depth: 2513 feet

Operator License No.: 33864
Op Name: HABIT PETROLEUM, LLC
Address: 639 280TH AVE
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2513	0	w/unknown sxs cmt
SURF	8.625	1480	0	w/unknown sxs cmt <u>81.67</u>

Well Type: OH DH *KCC per 2/13* UIC Docket No: _____ Date/Time to Plug: 11/14/2008 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: J.R. HASELHORST Company: HABIT PETROLEUM, LLC Phone: (785) 625-6190

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel - 500# hulls.
Hole full with drilling mud.
Unable to get back into 5 1/2" casing at 2513'. Decided to P/A.
Lost tapper mill and one joint tubing at 2496'.
Pulled 5 1/2" per 1969 plugging report.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/14/2008 11:00 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 2123'. Allied pumped 50 sxs 60/40 pozmix - 4% gel with 200# hulls.
Pulled to 1525' - pumped 40 sxs cement with 100# hulls.
Pulled to 875' - pumped 80 sxs cement with 200# hulls.
Pulled to 40' - pumped 10 sxs cement - hole full of cement.
Note: Left tapper mill and one joint tubing at 2496'.

Perfs:

INVOICED

DATE 12-19-08
INV. NO. 2009060865

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 20 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

CM

PT