

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 033-21472-0000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

Indicate original spud or completion date 11/7/06

Well Operator: Woolsey Operating Company LLC KCC License #: 33168
(Owner / Company Name) (Operator's)

Address: 125 N Market #1000 City: Wichita

State: Kansas Zip Code: 67202 Contact Phone: (620) 886 - 5606 ext 27

Lease: Shane Yost Well #: 15 Sec. 10 Twp. 31 S. R. 17 East West

120' W - S2 - S2 - SE Spot Location / QQQQ County: Comanche

330' Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1440' Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well

SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: 20" Set at: 66' Cemented with: 10.5 yards grout KCC PWT Sacks

Surface Casing Size: 10 3/4" Set at: 285' Cemented with: 350 250 Per CP 213 Sacks

Production Casing Size: 4 1/2" Set at: 5368' Cemented with: 160 Sacks

List (ALL) Perforations and Bridgeplug Sets: 4997' to 5016' 4380 Tagged cement.

Elevation: 2056' (G.L. / K.B.) T.D.: 5380 PBTD: 5323' Anhydrite Depth: 1170' 85 ft
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): As per KCC recommendation

Pump bottom plug w/ 200# hulls + 205x.cmt. Top plug = 1st plug @ 990 w/ 155x.gel + 505x.cmt.
2nd plug @ 310' w/ 75x.cmt. 3rd plug @ 40' w/ 255x.cmt. 60/40 p/z 4 gel S.P.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Carl W. Durr

Phone: (620) 886 - 5606 ext 27

Address: 1966 SE Rodeo Drive PO Box 168 City / State: Medicine Lodge, Ks

Plugging Contractor: Pratt Well Service KCC License #: 5893
(Company Name) (Contractor's)

Address: Pratt, Kansas Phone: (620) 672 - 2531

Proposed Date and Hour of Plugging (if known?): 11-25-08 8:00 AM

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 1/15/08 Authorized Operator / Agent: _____
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

**RECEIVED
DEC 15 2008
KCC WICHITA**

*Well Plugged - KCC-PKT

100 + Coline
2W 3N 5W 2N.
Dist 1
PCT

Quality Well Service, Inc.

190 US Highway 56
Ellinwood, KS 67526

Invoice

Date	Invoice #
12/8/2008	1032

Bill To
Woolsey Operating Company LLC 125 N Market, #1000 Wichita, KS 67202

P.O. No.	Terms	Lease Name
		Shane Yost 15

Description	Qty	Rate	Amount
Rig Time	26.5	190.00	5,035.00T
Floor Rental		125.00	125.00T
Shots	3	300.00	900.00T
Torch		75.00	75.00T
Water Truck	5.5	85.00	467.50T
Backhoe	4.5	85.00	382.50T
Out of Town		120.00	120.00T
Phone Calls		25.00	25.00T
Clerical		25.00	25.00T
Wiping Rubber		20.00	20.00T
Fresh Water	2	20.00	40.00T
Subtotal			7,215.00
7% Fuel Surcharge		7.00%	505.05T
<p>11-21-08 Drove to location, raised pole, rigged up to 4 1/2" casing, pumped 25 sacks, 200# hulls, displaced to 4380', max pressure 500 psi, shut in 250 psi, drove home.</p> <p>11-24-08 Drove to location, checked hole, tagged cement at 4380', dug cellar, unpacked casing head, set floor, pulled slips, cut surface off 4' below ground, had 9" stretch, ripped casing at 4000', worked pipe, ripped casing at 3810', worked pipe, ripped casing at 3640', worked pipe free, pulled casing up to 990', swedge in, drove to motel.</p> <p>11-25-08 Drove to location, pumped 15 gel, 50 sacks, 50# hulls at 990', pulled to 310', pumped 75 sacks, 50# hulls, pulled to 40', pumped 25 sacks to surface, tore down floor and rig, emptied pit, cleaned up location.</p>			
Subtotal			\$7,720.05
Sales Tax (5.3%)			\$409.16
Total			\$8,129.21

RECEIVED
DEC 15 2008
KCC WICHITA