

6 070423

API NUMBER 15-193-20, 379-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE-NE-SW, SEC. 30, T. 10 S, R. 22 W
1740 feet from S section line
2980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181
Operator: DONALD C SLAWSON
Name & Address: 200 DOUGLAS BLDG.
WICHITA, KANS. 67202
BILL MORIGAN

Lease Name HARLIN G.G. Well # 1
County THOMAS. 153.66
Well Total Depth 4728 feet
Conductor Pipe: Size 0 feet
Surface Casing: Size 8 5/8 feet 343

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor SLAWSON DRUG. Co. License Number 5657

Address 200 DOUGLAS BLDG. WICHITA, KANS. 67202

Company to plug at: Hour: 6:00 PM Day: 27th Month: NOV Year: 1985

Plugging proposal received from BOB ROWE

(company name) SLAWSON DRUG. INC (phone) 316-263-3201

were: 8 5/8" - 343 ft 3% cement / 250' 60' 1/4 Pozmix 6% GEL - CACL (BY HALLIBURTON)

ORDER 205' 60' 1/4 Pozmix GEL - CACL - 1' SK 3/4" CELE AND 8 5/8" PLUG.

SPOT WITH DRILL STEM, RECONDITION HOLE (VISCOSITY) HEAVY MUD BETWEEN ALL PLUGS

MISS WELL, ELV. 3078, INHY 2586, NO CIRCULATION PROBLEMS

MUD CONDITION 44 VISCOSITY, WEIGHT 9.2, WATER LOSS 8.8.

Plugging Proposal Received by Morrison Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 6:00 PM Day: 27th Month: NOV Year: 1985

ACTUAL PLUGGING REPORT Ordered 205' 60' 1/4 Pozmix 3% GEL, 1' SK 3/4" CELE, AND 8 5/8" PLUG

SPOTTED WITH DRILL STEM RECONDITIONED HOLE, HEAVY MUD BETWEEN ALL PLUGS.

1st Plug @ 2610 FT 3/30 SK Cmt, 2nd Plug @ 1770 FT 1/100 SK cmt 1/2 SK cels.

3rd Plug @ 350 FT 1/50 SK Cmt, 4th Plug SOUTH BRIDGE HULLS-PLUG @ 40' TO 1/10 SK cmt.

15' IN RAT HOLE (CIRCULAR)
CEMENTED BY HALLIBURTON CMT.

Remarks: (if additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED STATE CORPORATION COMMISSION

DATE DEC 11 1985

DEC 9 1985

INV. NO. 1463

CONSERVATION DIVISION Wichita, Kansas

Signed Morrison Schmidt (TECHNICIAN) DOK

FORM CP-2/3 Rev. 01-84

3 12-6-85 mgl.