

11-30

4-060475

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-193-20,618-0000

NE NW SE /4 SEC. 29, 10 S, 32 W  
2310 feet from S section line  
1650 feet from E section line

Operator license# 9860

Lease Eight "K" well # 1

Operator: Castle Resources, Inc.

County Thomas

150.80

Address: 1200 E. 27th Street  
Suite C  
Hays, Kansas 67601

Well total depth 4640 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 286 feet

Aband. oil well \_\_\_\_, Gas well \_\_\_\_, Input well \_\_\_\_, SWD \_\_\_\_, D & A X

Plugging contractor: Emphasis Oil Operations License# 8241

Address: Russell, Kansas 67665

Company to plug at: Hour: 7:45A.M. Day: 30 Month: November Year: 93

Plugging proposal received from: Tom Alm

Company: Emphasis Oil Operations Phone: \_\_\_\_\_

Were: Order 200 sxs. 60/40 posmix - 6% gel - 1/4# flocele per. sx.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour: 7:45A.M., Day: 30, Month: November, Year: 93

Actual plugging report:  
1st. plug at 2575' with 25 sxs. - Anhydrite 2567' - 2610'.  
2nd. plug at 1775' with 100 sxs. - Dakota 1462' - 1762'.  
3rd. plug at 340' with 40 sxs. - Surface pipe set to 286'.  
4th. plug at 40' with 10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

Remarks: Halliburton Cementing.  
Condition of casing(in hole): GOOD X BAD \_\_\_\_\_ Anhy. plug: YES X NO \_\_\_\_\_ STATE \_\_\_\_\_  
Bottom plug(in place): YES \_\_\_\_\_, CALC \_\_\_\_\_, NO X Dakota plug: YES X, NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING \_\_\_\_\_. Elevation: 3062 GL \_\_\_\_\_

I did[ ] / did not[ X ] observe the plugging.

**INVOICED**

DATE DEC 13 1993  
INV. NO. 39489

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 10 1993  
CONSERVATION DIVISION  
Wichita, Kansas  
Form CP-2/3  
o/k JLB (agent)