

6 030613

API NUMBER 15-193-20,382-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SWSENW SEC. 36, T. 10 S., R. 32 W

2970 feet from (S) section line

3630 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5063

Lease Name GEORGE Well # 1

Operator: ENERGY EXPLORATION INC.

County THOMAS

Name & Address 1002 S. BROADWAY

Well Total Depth 4700 152.75 feet

WICHITA, KANSAS

Conductor Pipe: Size _____ feet

67211

Surface Casing: Size 8 5/8 feet 303

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor ABERCROMBIE ORLG INC. License Number _____

Address WICHITA, KANSAS

Company to plug at: Hour: AM Day: 16 Month: 12 Year: 19 85

Plugging proposal received from WALLY TOWNES

(company name) ABERCROMBIE ORLG. INC. (phone) _____

were: 8 5/8 SET @ 303' w/2 1/2 SX. CONDITION HOLE WITH NO LESS THAN 36 UIS,
MUD w/NO LOSS OR GAIN OF FLUID SPOT CEMENT PLUGS w/DRILL PIPE
ORDER 200 SX. 60/40 PER 6 LOGEL 3% CC 8 5/8 W.P. BJTITAN CMT. CO.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:30AM Day: 16 Month: 12 Year: 19 85

ACTUAL PLUGGING REPORT SPOT D.P. @ 2550' DISPLACE 25 SX. CMT. MIX. LAYDOWN
D.P. TO 2250' DISPLACE 100 SX. CMT. MIX. + 1 SX. HULLS LAYDOWN D.P.
TO 325' DISPLACE 40 SX. CMT. MIX. LAYDOWN D.P. PUSH W.P. TO
KELLY DEPTH DUMP 1/2 SX. HULLS & 10 SX. CMT. MIX. TO BASE OF CELLAR
DISPLACE 15 SX. IN RATHOLE & 10 SX. IN MOUSE HOLE w/JOINT OF PIPE
PLUG. COMP.

Remarks: ELEV. 3005 ANHY 2540-72
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging. STATE CORPORATION COMMISSION

Signed Carl Goodrow
(TECHNICIAN)

14
12-20-85
mas

DATE DEC 23 1985

DEC 23 1985

INV. NO. 11706

FEBCONS 5-1986 DIVISION