

4-071122

9-28

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-193-20,361-0000

NE SW SE /4 SEC. 36, 10 S, 32 W
990 feet from S section line
1650 feet from E section line

Operator license# 5131

Lease Nichols well # 1

Operator: Thunderbird Drilling, Inc.

County Thomas

Address: P.O. Box 97
Ellinwood, Kansas 67526
Maynard Weber

Well total depth 4700 feet ^{152.75}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 301 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing Kelso Casing Pulling License# 6050

Address: Hays, Kansas 67601

Company to plug at: Hour: P.M. Day: 28 Month: September Year: 94

Plugging proposal received from: Claud Blakesley

Company: Thunderbird Drilling, Inc. Phone: 316-564-2577

Were: 8 5/8" - 301' S.P. cwc. w/N/A sxs. cmt. 5 1/2" csq. set @ 4699'
w/250 sxs. cmt. D.V. tool at 2528' cwc. w/425 sxs. cmt. Csq. good.
Elv. 3041' - P.B.T.D. 4210' - Anhy. 2560'. Proposal 300 sxs. 60/40
pozmix - 10% gel - 5 sxs. hulls. - 12 sxs. Bentonite gel. Pump in with
pump truck. Load both 5 1/2" casing and 5 1/2" x 8 5/8" annulus with
cement and shut in under pressure.

Plugging Proposal Received by: Dennis Hamel
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 2:10P.M., Day: 28, Month: September, Year: 94

Actual plugging report: Thunderbird Drilling ordered 300 sxs. 60/40
pozmix - 10% gel and 12 sxs. Bentonite gel and 5 sxs. hulls.
Pumped in with pump truck.

1) Pumped in 8 sxs. cement in 5 1/2" x 8 5/8" annulus. Max. pressure
500# P.S.I. Shut in @ 300# P.S.I.

2) Pumped in 5 1/2" casing with 50 sxs. cement with 3 sxs. hulls. Then
12 sxs. Bentonite gel then 165 sxs. cement with 1 sx. hulls added.
Max. pressure 1500# P.S.I. Shut in at 1200# P.S.I.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: 3041

I did / did not observe the plugging.

INVOICED

DATE 10-10-94

INV. NO. 41387

RECEIVED
STATE CORPORATION COMMISSION
OCT 05 1994
(agent)

Form CP-2(3)