

278

6 030929

AUG 16 1987

API NUMBER 15- 193-20,443-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NW SE SW, SEC. 36, T. 10 S, R. 32 W/2
990 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422

Lease Name Double S Well # 1

Operator: Brito Oil Co. Inc.

County Thomas 132.28

Name & Address 200 East First

Well Total Depth 4070 feet

Suite 413

Conductor Pipe: Size feet

Wichita, Kansas 67202

Surface Casing: Size 8 5/8 feet 330

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling License Number 5422 4629

Address Wichita, Kansas 67202

Company to plug at: Hour: AM Day: 16 Month: August Year: 19 87

Plugging proposal received from Bill Craig

(company name) Abercrombie Drilling (phone)

were: Order 200 sks 60/40 Pozmix 6% Gel 3% Ca Cl. 1 sks Hulls and 8 5/8" plug

Spot with drill pipe with no less than 36 vis. mud between all plugs, with

good circulation and no fluid loss. B. J. Titan Cmt. Co.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:30AM Day: 16 Month: August Year: 19 87

ACTUAL PLUGGING REPORT

1st plug at 2580' w/25 sks.

2nd plug at 1700' w/100 sks and 1 sk Hulls

3rd plug at 380' w/ 40 sks

4th plug at 40' w/10 sks

15 sks in rat hole, 10 sks in mouse hole.

Remarks: Elev. 3035 G. L. Anhy. 2576' - 2608'

(if additional description is necessary, use BACK of this form.)

INVOICED (XXX) did not observe this plugging.

DATE 9-15-87

Signed Carl Goodrow (TECHNICIAN) Carl Goodrow

INV. NO. 18105

RECEIVED STATE CORPORATION COMMISSION 9-8-87 SEP 8 1987

CONSERVATION DIVISION Wichita, Kansas