

6 070885

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 193-20,537-0000

100 N W/2 SW SEC. 8, T 10 S, R 33 W/EX

1420 feet from S section line,

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # Brito Oil Co

Lease Name Regier Well # 2-8

Operator: 200 E. First #208

County Thomas 155.35

Name & Address Wichita, Ks. 67202

Well Total Depth 4780 feet

Paul F. Brito

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 352

Abandoned Oil Well Gas Well Input Well SWD Well D&A xx

Other well as hereinafter indicated

Plugging Contractor Blue Goose Drilling License Number

Address Great Bend, Ks.

Company to plug at: Hour: AAM Day: 6 Month: Dec. Year: 19 90

Plugging proposal received from Blue Goose Drilling

(company name) Blue Goose Drilling (phone)

were: 8 5/8 352 ft. S.P. cwc w/195 sks 60/40 poz 3% cc 2% gel. By Allied Cement.

Miss well. No cir problems. Mud condition 45 vis. 9 weight. 10 water loss. Elv.

3206. Anhy 2708. Proposal 200 sks 60/40 poz 6% gel 35 cc and 1 sk f.c. Spot with drill

stem, circ. Heavy mud between all plugs. 25 sks at 2715. 100 sks w/1 sks f.c. at 1860.

50 sks at 400 ft. 10 sks at 40 ft. 15 sks in rathole. Circ.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None xx

Operations Completed: Hour: 3:00 PM Day: 6 Month: Dec. Year: 19 90

ACTUAL PLUGGING REPORT Blue Goose ordered 200 sks 60/40 poz 6% gel 3% cc and 1 sk f.c.

Circ. Spotted cement with drill stem. Heavy mud between all plugs.

1st plug at 2715 w/25 sks cement.

2nd plug at 1860 w/100 sks cement w/1 sk f.c.

3rd plug at 400 ft. w/50 sks cement.

4th plug at 40 w/10 sks cement 15 sks rathole circ. by Allied Cement.

Remarks:

INVOICED

(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

DATE 1-8-91

INV. NO. 30404

J.P.S.

Signed Marion J. Schmidt (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
12-16-90
DEC 16 1990
CONSERVATION DIVISION
Wichita, Kansas