

TO
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 Bitting Building
Wichita, Kansas

File 86-9

Location SWc NW NW

Sec. 9 Twp. 27Rge. 2E

I have today completed supervision of plugging of:

Well No. 1 (SWD WELL) Lease Feik

Operator National Refg. Co. Address 304 Kaufman Bldg.

Field Eastborough, North County Sedgwick

Total Depth 2312 Feet. 2312' is the plugged back total Depth of this well. It was plugged back and made into a Salt Water Disposal Well.
(Describe briefly the manner in which well was plugged)

5" pipe was set and cemented at 2132'. The hole was filled with heavy mud to bottom of 5" and bridged with rock and cemented with 5 sacks of cement. Pulled 5" casing and filled hole with heavy mud to 122'. Hole bridged with wood plug and rock and cemented with 15 sacks of cement. Hole filled to top and capped with 5 sacks of cement. Cellar filled with soil.

Expense incurred as follows:

Date Dec. 11, 1939 *Day 2/4 Mileage 48 (two trips)

Date Dec. 12, 1939 *Day 2/4 Mileage 41 (two trips)

Date _____ *Day 4/4 Mileage 89

Hotel, meals, etc. \$ _____

*Show as 1/4, 2/4, 3/4, or 4/4.

F. D. Carter
Conservation Agent
F. D. Carter.

P. O. Wichita, Kansas Date December 14, 1939

PLUGGING
FILE 86-9-27-2E
BOOK PAGE 86 LINE 9

RECEIVED
DEC 14 1939
STATE CORP. COMM.
CONSERV. DIV.