

KANSAS

Form CP-3,  
Rev. 6-26-62

4 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-065-30209-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 20 1966  
12-20-66  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Burch Exploration, Inc.,

Complete Address: 1011 Union Center, Wichita, Kansas.

Lease Name Ninemire Well No. 1

Location NW-NW-NW Sec. 23 Twp. 9 Rge. (E) (W) 23

County Graham Total Depth 3900

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Abercrombie Drilling, Incorporated,

Address: 801 Union Center, Wichita, Kansas. License No.     

Operation Completed: Hour 7:00AM Day 15 Month 12 Year 1966

The Above well was plugged as follows:

226'--7" OD casing, cement circulated. (6 1/8" hole).

Circulated hole with heavy mud, set plug @ 550' and displaced 15 Sx.

cement thru DP. Heavy mud to 210', set plug with 1/4 sack hulls and dis-

placed 15 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack hulls

and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/20/66

INV. NO. 4494-w

Signed: A. L. Nichols  
Well Plugging Supervisor