

KANSAS

70

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 5 1971
CONSERVATION DIVISION
Wichita, Kansas

02-05-1971

15-193-20035-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name National Cooperative Refinery Association,
Complete Address Box #6, Great Bend, Kansas.
Lease Name Huelsmann Well No. 1
Location CNE-NE Sec. 20 Twp. 10 Rge. (E) (W) 32
County Thomas Total Depth 4710'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Red Tiger Drilling Company,
Address 1720 Wichita Plaza Building, Wichita, Kansas. License No.
Operation Completed: Hour 11:00 PM Day 2 Month 2 Year 1971

The above well was plugged as follows:

283'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1500'.

Circulated hole with heavy mud. Pulled DP to 1775' and displaced 115 Sx. cement thru
DP from 1775' to 1400'. Pulled DP to 310' and displaced 25 Sx. cement thru DP from
310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 2/5/71
INV. NO. 3305-W