

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15- 167-21, 726-00-00

200 Colorado Derby Bldg.  
Wichita, KS 67202

Operator's Full Name MAI OPERATIONS

Complete Address BOX 33 RUSSELL, KANS., 67665

Lease Name VESTAL HALL Well No. #1

Location C-NE Sec. 25 Twp. 11 Rge. 13 (East) (West)

County RUSSELL Total Depth 3780 FE

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor SHIELDS DRILLING COMPANY, INC.

Address BOX 709 SHIELDS BLDG, RUSSELL, MO. License No. \_\_\_\_\_

Operation Completed: Hour: 4:30 AM Day: 12<sup>th</sup> Month: AUG. Year: 1981

Plugging Operations attended by Agent? All  Part  None

The above well was plugged as follows:

- 8 5/8" - 267 FE SP. CUL. w/ 160 ST QUICK SET.
- ORDERED 130 ST 50 PERMIX 4% GEL - 3% CA-CL. + 8 5/8" PLUG.
- SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.
- 1 ST PLUG. @ 570 FE w/ 70 ST CMT.
- 2 ND PLUG. @ 240 FE w/ 40 ST CMT.
- 3 RD PLUG. -> SLID BRIDGE @ 40 FE / 0 w/ 10 ST CMT.
- 5 ST IN BAT HOLE.
- 5 ST IN MOUSE HOLE.

RECEIVED  
STATE CORPORATION COMMISSION

CEMENTED BY ALLIED AUG 14 1981

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Conservation Division Agent

INVOICED

DATE 9-28-81

INV. NO. 7625-W