

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-167-21,914-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Corie Oil Operations

Complete Address R. R. #1, Box 83, Russell, Kansas 67665

Lease Name Scott Well No. #1

Location NW NW SE Sec. 22 Twp. 11 Rge. 14 (East) ~~(West)~~

County Russell Total Depth 3319'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations

Address Box 506, Russell, Kansas 67665 License No. _____

Operation Completed: Hour: 7:30AM Day: 17th Month: May Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8"-253' s.p. cuc. w/160 common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spot with drill stem with heavy mud between all plugs.

1st plug @ 660' w/70 sacks cement

2nd plug @ 260' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement.

Circulate 10 sacks of cement in rat hole.

Amount of Surface Casing: 253' of 8 5/8".

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. ~~A full account for my not being present is as follows:~~

I was at 9-12-17 Ellis County plugging a well at this time.

RECEIVED
STATE CORPORATION COMMISSION
MAY 24 1982
5-24-1982
CONSERVATION DIVISION
Wichita, Kansas

Signed: [Signature]
Conservation Division Agent
INVOICED
DATE 6-3-82
INV. NO. 323-W