

15-167-00253-00-00

17

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 34-1

LOCATION SW NW SE

SEC 26 TWP. 11 RGE. 15

Dry Hole  Abandoned Oil Well  Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. 1 Lease ~~Eulert~~ Eulert

Operator B - H - P Oil Co Address Great Bend, Kans *Box 67*

Field Eulert County Russell

Total Depth 3385 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 360' circulated with cement - 5 1/2" at 3370' with  
100 sax cement behind.

Lane wells plugs to 2975', top perf at 2765'.

Filled with sand to 2750', set 5 sax cement with dump bailer,  
pulled 2700' 5 1/2", filled hole with heavy mud to 250', set  
rock bridge and 15 sax cement, filled with heavy mud to  
40' set rock bridge and 10 sax cement to bottom-cellar.

**RECEIVED**  
STATE CORPORATION COMMISSION  
10-27-1950  
OCT 27 1950  
CONSERVATION DIVISION  
Wichita, Kansas

*E. Perry*  
District Conservation Agent

Date 10-25-50

**PLUGGING**  
FILE SEC 26 T 11 R 15  
BOOK PAGE 34 LINE 1