

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
 OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
 K.A.R. 82-3-117

Form CP-4  
 December 2003  
 Type or Print on this Form  
 Form must be Signed  
 All blanks must be Filled

Lease Operator: American Warroir inc.  
 Address: P.O. Box 399 Garden City Ks. 67846  
 Phone: (620) 272-1023 Operator License #: 4058  
 Type of Well: Oil Docket #: \_\_\_\_\_  
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
 The plugging proposal was approved on: 10/29/08 (Date)  
 by: Pat Staab (KCC District Agent's Name)  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (if needed attach another sheet)  
Arbuckle Depth to Top: 3332' Bottom: NA T.D. 3347'  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
 \_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-009-22315-00-00  
 Lease Name: Hoffman  
 Well Number: #5  
 Spot Location (QQQQ): C - NE - NW - NW  
4950' 4879' Feet from  North /  South Section Line  
4280' 4817' Feet from  East /  West Section Line  
 Sec. 2 Twp. 17 S. R. 12  East  West  
 County: Barton  
 Date Well Completed: 12/2/81  
 Plugging Commenced: 10/29/08  
 Plugging Completed: 10/29/08

KCC  
 PKT  
 per  
 OPS.

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	oil	319'	surface	85/8	319'	0
		3345'	surface	51/2	3345'	0#

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf 1450', 789', 369', 2spf. Ran tbg to 1988'. Swift hooked up to tbg, mixed and pumped 180sx 60/40 pos 4% gel w/ 400# hulls. Cement circulated to surface. Pull tbg. Swift hooked up to 4 1/2 casing, mixed and pumped 20sx 60/40 pos 4% gel w/ 100# hulls. Cut casing off 6' below surface and back filled.

express well service + supply Inc  
 Name of Plugging Contractor: Swift Services Inc. License #: 785-798-2300  
 Address: P.O. Box 466 Nesscity Ks. 67560  
 Name of Party Responsible for Plugging Fees: American Warrior Inc.  
 RECEIVED KANSAS CORPORATION COMMISSION  
 NOV 17 2008  
 CONSERVATION DIVISION WICHITA, KS

State of Kansas County, Finney, ss.  
Jody Smith (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

**ERICA KUHLMIEIER**  
 Notary Public - State of Kansas  
 My Appt. Expires 09/22/09

(Signature) [Signature]  
 (Address) P.O. Box 399 Garden City Ks. 67846

SUBSCRIBED and SWORN TO before me this 12 day of November 20 08  
[Signature] My Commission Expires: 09/22/09  
 Notary Public

[Handwritten initials]