

15-167-22193-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Russell SEC. 25 TWP. 11S RGE. 15 E/W  
Location as in quarters or footage from lines:  
1650' FNL & 850' FEL of NE/4


Locate Well  
correctly on above  
Section Platt.

Lease Owner E S P Development  
Lease Name Morril Well No. 1  
Office Address c/o Lewis Eulert, Paradise, Kansas 67658  
Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
Date Well Completed 8-26-83  
Application for plugging filed 8-26-83  
Plugging commenced 8-26-83  
Plugging completed 8-26-83  
Reason for abandonment of well or producing formation Dry Hole

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ed Shoemaker  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3550'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8	245'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

- 20 sks cement @ 3550'
- 20 sks cement @ 985'
- 80 sks cement @ 510'
- 40 sks cement @ 290'
- 10 sks cement @ 40'
- 10 sks cement @ rathole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Emphasis Oil Operations

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Joe K. Branum (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed **RECEIVED** the same are true and correct. So help me God.

STATE CORPORATION COMMISSION

9-2-1983  
SEP 2 1983

(Signature) Joe K. Branum  
P.O. Box 506, Russell, KS 67665-0506  
(Address)

CONSERVATION DIVISION  
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 30th day of August, 19 83

Glenda R. Tiffin  
Glenda R. Tiffin, Notary Public.

My Commission expires: February 6, 1984

15-167-22193-00-00

EMPHASIS OIL OPERATIONS

P. O. Box 506

Russell, Kansas 67665-0506

DRILLERS LOG

OPERATOR: E S P Development  
c/o Lewis Eulert  
Paradise, Kansas 67658

CONTRACTOR: Emphasis Oil Operations  
P. O. Box 506  
Russell, Kansas 67665-0506

LEASE: Morrill WELL: #1

LOCATION: 1650' FNL & 850' FEL of NE/4  
Section 25-11S-15W  
Russell County, Kansas

Total Depth: 3550'

Elevation: 1888' K.B.

Commenced: 8-19-83

Date Completed: 8-26-83

Casing: 8-5/8 @ 245' with 150 sks cement

Status: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Top Soil & Sand	30'	Shale	2225'
Sand & Shale	248'	Shale & Lime	2445'
Shale, Clay & Pyrite	515'	Shale	2855'
Shale & Sand	976'	Lime & Shale	3110'
Anhydrite	1009'	Lime (R.T.D.)	3550'

STATE OF KANSAS )  
                          ) ss:  
COUNTY OF RUSSELL)

Joe K. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

*Joe K. Branum*  
 \_\_\_\_\_  
 Joe K. Branum STATE CORPORATION COMMISSION  
 RECEIVED  
 9-2-1983  
 SEP 2 1983  
 CONSERVATION DIVISION  
 Wichita, Kansas

Subscribed and sworn to before me this 30th day of August, 1983.  
My Commission Expires: February 6, 1984.



*Glenda R. Tiffin*  
 \_\_\_\_\_  
 Notary Public