

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

15-193-00012-00-00
WELL PLUGGING RECORD

Thomas County, Sec. 26 Twp. 10 Rge. 32 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW NE
Lease Owner H. K. Riddle
Lease Name Albers Well No. 1
Office Address P. O. Box 1055, Albuquerque, New Mexico
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 3, 19 52
Application for plugging filed " 19
Application for plugging approved " 19
Plugging commenced " 19
Plugging completed " 19
Reason for abandonment of well or producing formation dry

NORTH

| | | | |
|--|---|---|--|
| | | 0 | |
| | | | |
| | 2 | 6 | |
| | | | |

Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 4770 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|-----|-------|--------|------------|
| | | 0 | 224 | 8 5/8 | 224 | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4770) back to 210' heavy rotary mud with one plug and 15 sacks cement. 210' back to 45' heavy rotary mud with one plug and 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Buick Drilling Inc.
Address Box 331, St. John, Kansas

STATE OF Kansas, COUNTY OF Stafford, ss.
H. R. Buick (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *H. R. Buick*

Box 331, St. John, Kansas
(Address)


SUBSCRIBED AND SWORN to before me this 3rd day of December 19 52

My commission expires
December 26, 1955

My commission expires

23-8390-s

6-51-20M



RECEIVED
STATE CORPORATION COMMISSION

DEC - 5 1952
12-05-1952
CONSERVATION DIVISION
Wichita, Kansas

Notary Public.

15-193-00012-00-00

DRILLER'S LOG

Albers #1

NW NW NE

Commenced R.D.: 11-14-52

Sec. 26-10-32

Completed R.D.: 12-3-52

Thomas County, Kansas

Total Depth: 4770'

Elevation: 3049' D.F.

Casing Record: 224' 8 5/8"

Initial Prod.: None

Contractor: Buick Drilling Inc.

STRATA

DEPTH

| | |
|---------------------------|-------------------|
| Surface and Clay | 0 - 70 |
| Sand and Gravel | 70 - 140 |
| Clay | 140 - 145 |
| Sand | 145 - 180 |
| Shale | 180 - 224 |
| Blue Shale | 224 - 470 |
| Blue and Gray Shale | 470 - 1045 |
| White Clay and Shells | 1045 - 1115 |
| Shale and Shells | 1115 - 1510 |
| Sand and Shale | 1510 - 1950 |
| Sand and Shells | 1950 - 2120 |
| Shale | 2120 - 2155 |
| Shale and Shells | 2155 - 2475 |
| Red Bed, Sandy | 2475 - 2587 |
| Anhydrite | 2587 - 2610 |
| Red Bed, Shale | 2610 - 2700 |
| Shale and Shells | 2700 - 2815 |
| Red Bed, Shale and Shells | 2815 - 2990 |
| Shale and Shells | 2990 - 3090 |
| Shale and Lime | 3090 - 3715 |
| Lime | 3715 - 4000 |
| Lime and Shale | 4000 - 4235 |
| Lime | 4235 - 4295 |
| Lime and Shale | 4295 - 4535 |
| Lime | 4535 - 4537 |
| Broken Lime | 4537 - 4570 |
| Lime | 4570 - 4655 |
| Shale and Lime | 4655 - 4760 |
| Lime | 4760 - 4770 T. D. |

I hereby certify the above a true and correct drilling log as reflected by the drilling reports of the Buick Drilling Inc.

BUICK DRILLING INC.

H. R. Buick
H. R. Buick, President

Signed and sworn to in my presence this 3rd day of December, 1952, by H. R. Buick, President of the Buick Drilling Inc.

Roberta Shogren
Notary Public

My Commission Expires: December 26, 1955

PLUGGING
FILE SEC 26 T 10 R 322
BOOK PAGE 63 LINE 26

12-05-1952
Wichita, Kansas