

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas. 67202

WELL PLUGGING RECORD #6
K.A.R.-82-3-117

API NUMBER 15-193-2041 ^{20,401-00-00}
LEASE NAME Krug

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 2
2970 Ft. from S Section Line
330 Ft. from E Section Line
SEC. 27 TWP. 10 SRGE. 32 ~~(S)~~ or (W)
COUNTY Thomas
Date Well Completed 4/1/86
Plugging Commenced 4/1/86
Plugging Completed 4/1/86

LEASE OPERATOR JAY BOY OIL, INC.

ADDRESS 8400 Killarney, Wichita, KS. 67206

PHONE# (316) 263-5781 OPERATORS LICENSE NO. 4569

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist #6 Carl Goodrow

Is ACO-1 filed? Yes If not, is well log attached? N/A

Producing Formation N/A Depth to Top N/A Bottom N/A T.D. LTD 4673'
RTD 4677'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From 8'	To 304'	Size 8 5/8" 23#	Put in 296'	Pulled out None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

1st Plug 4320'-4030' (Lsg-KC) 95 sx 60-40 Pozmix 2% gel; 2nd Plug @2580' (Anhy) 20 sx 60-40 Pozmix w/6% gel 3% CaCl2; 3rd Plug @1740' (Dakota) 100sx 60-40 Poz 6% gel 1% Flocele 3% CaCl2 4th Plug 340' w/40 sx 60-40 Poz 6% gel 3% CaCl2, 40'-Solid wood plug w/10 sx cmt a/a to suf. RH-15 sx a/a
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. _____

Address Box 47, Oberlin, KS. 67749

STATE OF Kansas COUNTY OF Sedgwick, ss.

I, C.K. Morriosn

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so I hereby certify.

RECEIVED
STATE CORPORATION COMMISSION

(Signature) C.K. Morriosn

(Address) Jay Boy Oil, Inc.
8400 Killarney, Wichita, Ks 67206

Subscribed and sworn to before me this 6th day of May, 19 86

Betty B. Herring
Notary Public

BETTY B. HERRING
NOTARY PUBLIC
STATE OF KANSAS
My Appt. Exp. 10-07-89

MAY 6 - 1986
05-06-1986
Wichita, Kansas

My Commission Expires: 10-07-89