

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-193-20,604-00-00

LEASE NAME Peck

WELL NUMBER #1

3300 Ft. from (S) Section Line

4950 Ft. from (E) Section Line

SEC. 28 TWP. 10S RGE. 32W (E) or (W)

COUNTY Thomas

Date Well Completed 11-21-92

Plugging Commenced 11-21-92

Plugging Completed 11-21-92

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR The Dane G. Hansen Trust

ADDRESS P.O. Box 187, Logan, Kansas 67646

PHONE# (918) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 21, 1992 (date)

by David Wann (KCC District Agent's Name).

Is ACO-1 filed? Yes if not, is well log attached? _____

Producing Formation none Depth to Top --- Bottom --- T.D. 4690'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	348'	=0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set

Plugged w/200 sx 60/40 pozmix, 6% gel, 2 sx floreal & 8 5/8" wipper plug.
Plug @ 2580' w/25 sx, 1765' w/100 sx, 380' w/40 sx, 40' w/10 sx,
15 sx in rathole, 10 sx in mousehole.

Name of Plugging Contractor Chief Drilling, Inc. License No. 5886

Address 120 S. Market #300, Wichita, Kansas 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: The Dane G. Hansen Trust

STATE OF Kansas COUNTY OF Phillips, ss.

Dane G. Bales, Manager (Employee of Operator) ~~xxxx Operator~~

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Dane G. Bales

(Address) P. O. Box 187, Logan, Kansas 67646

SUBSCRIBED AND SWORN TO before me this 8th day of December 1992



Betty Jane Bittel Notary Public DEC 22 1992
 My Commission Expires: July 17, 1996.

USE ONLY ONE SIDE OF EACH FORM

12-22-1992
 Form CP-4
 Revised 05-88