

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-193-206410000

LEASE NAME George

TYPE OR PRINT

NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER #1

3170  
2970 Ft. from S Section Line

4950 Ft. from E Section Line

LEASE OPERATOR Coral Coast Petroleum, L.C.

SEC. 36 TWP. 10 RGE. 32 ~~W~~ or (W)

ADDRESS 212 N. Market, #402, Wichita, KS 676202

COUNTY Thomas

PHONE#(316) 269-1233 OPERATORS LICENSE NO. 31691

Date Well Completed 12/13/95

Character of Well D&A LH

Plugging Commenced 12/13/95

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12/13/95

The plugging proposal was approved on 12/13/95 (date)

by Ken Kuhn (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 2620 Ft.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS RECEIVED STATE CORPORATION COMMISSION CASING RECORD

Formation Surface	Content	To	Size	Put in	Pulled out
	<u>305'</u>	<u>0'</u>	<u>8-5/8"</u>	<u>305'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plugged with 200 sacks 60/40 Pozmix, 6% gel, 1/4# floxal per sack as follows: 25 sx @ 2620', 100 sx @ 1740', 40 sx @ 355', 10 sx @ 40', 15 sx rathole, 10 sx mousehole. P.D. @ 9:15 p.m. 12/13/95.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Mallard JV, Inc. License No. 4958

Address P. O. Box 1009, McPherson, KS 67460

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Coral Coast Petroleum, L.C.

STATE OF Kansas COUNTY OF Sodgwick, ss.

Daniel M. Reynolds (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Daniel M. Reynolds

(Address) 212 N. Market #402

SUBSCRIBED AND SWORN TO before me this 22 day of January, 1996

Sharon K. Garrison  
Notary Public

