

KANSAS

24

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 20 1969
CONSERVATION DIVISION
Wichita, Kansas
02-20-1969

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-181-2005-00-00

Operator's Full Name Mack Oil Company,

Complete Address: 812 Union Center Building, Wichita, Kansas,

Lease Name Darnauer Well No. 1

Location CNW-NW Sec. 3 Twp. 10 Rge. (E) (W) 10

County Sherman Total Depth 5240'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Above

Address: _____ License No. _____

Operation Completed: Hour 4:30PM Day 18 Month 2 Year 1969

The Above well was plugged as follows:

360'--8 5/8" Surface casing, cement circulated with 350 Sx.
Dakota section from 1952' to 2054'.

Circulated hole with heavy mud. Pulled DP to 2075' and displaced 100 Sx. cement thru
DP from 2075' to 1750'. Pulled DP to 375' and displaced 20 Sx. cement thru DP from
375' to 315'. Pulled DP, set bridge @ 40' with $\frac{1}{2}$ sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *N. L. Nichols*
Well Plugging Supervisor

DATE 2/20/69
INV. NO. 9361-W