

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 3 1969
CONSERVATION DIVISION
Wichita, Kansas
02-03-1969

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-181-20004-00-00

Operator's Full Name Mack Oil Company,

Complete Address: 812 Union Center Building, Wichita, Kansas.

Lease Name Mary Browne Well No. 1

Location CNE-NE Sec. 10 Twp. 10 Rge. (E) (W) 41

County Sherman Total Depth 5330

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 5:30PM Day 31 Month 1 Year 1969

The Above well was plugged as follows:

376'--8 5/8" Surface casing, cement circulated with 300 Sx.
Top of Dakota section @ 2132'.

Circulated hole with heavy mud. Pulled DP to 2350' and displaced 120 Sx. cement thru
DP from 2350' to 1960'. Pulled DP to 400' and displaced 25 Sx. cement thru DP from
400' to 325'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Pichels
Well Plugging Supervisor

DATE 2/3/69
INV. NO. 9274-4