

14
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

15-181-30015-00-00

JUN 30 1964
06-30-1964
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Terrell Drilling & Producing,

Complete Address: Box #606, Russell, Kansas.

Lease Name Moore Well No. 1

Location CSW-SW Sec. 36 Twp. 10 Rge. (E) (W) 42

County Sherman Total Depth 5407

Abandoned Oil Well Gas Well Input Well SWD Well D & A x

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 6:30AM Day 25 Month 6 Year 1964

The Above well, was plugged as follows:

328'--8 5/8" Surface pipe, cement circulated with 250 Sx. Hole later
squeezed with 150 Sx. and 200 Sx.

Circulated hole with heavy mud, set plug @ 600' and displaced 20 Sx. cement
thru DP. Heavy mud to 315', set plug with 1/2 sack hulls and displaced 20
Sx. cement thru DP. Heavy mud to 35', set plug with 1/2 sk. hulls and 10 Sx.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 6/30/64

INV. NO. 9390-W