

15-193-20522-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 2/89

RECEIVED  
STATE CORPORATION COMMISSION

JUL 20 1990

WELL PLUGGING APPLICATION FORM  
(File One Copy)

CONSERVATION DIVISION  
Wichita, Kansas

API NUMBER 15-193-20,522 (of this well).  
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Brito Oil Co., Inc. OPERATOR'S LICENSE NO. 4629

ADDRESS 200 East First, Suite 208, Wichita, KS 67202 PHONE # (316) 263-8787

LEASE (FARM) Robben WELL NO. 1-10 WELL LOCATION NE NE NW COUNTY Thomas

SEC. 10 TWP. 10S RGE. 31 (E) or (W) TOTAL DEPTH 4650 PLUG BACK TD \_\_\_\_\_

Check One:

OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ D & A X SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8 SET AT 250 CEMENTED WITH 160 SACKS

CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

PERFORATED AT \_\_\_\_\_

CONDITION OF WELL: GOOD X POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING Fill hole with heavy mud: 1st plug at 2250 w/25 sx; 2nd plug at 1650' w/100 sx; 3rd plug at 300' w/40 sx; 4th plug at 40' w/10 sx; 15 sx in rathole. All cement 60/40 pozmix w/ 6% gel and 3% cc.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes \_\_\_\_\_ IS ACO-1 FILED? No \_\_\_\_\_  
(If not explain.) Sent to operator to complete

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 11:00 p.m. 7-13-90

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harold Maley PHONE # (913) 674-5768

ADDRESS 216 E. McFarland, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack F. Wharton  
(Operator or Agent)

DATE: July 19, 1990