

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

15-193-20475-00-00

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-193-20,475 (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Blackhawk Exploration, Inc. OPERATORS LICENSE NO. 4480

ADDRESS 200 E. First, Suite LL 100, Wichita, KS 67202 PHONE # (316) 265-6431

LEASE (FARM) Haverkamp WELL NO. 1 WELL LOCATION S/2 SW NW COUNTY Thomas

SEC. 14 TWP. 10S RGE. 31 ~~(E) (W)~~ TOTAL DEPTH 4665' PLUG BACK TO _____

Check One:

OIL WELL _____ GAS WELL _____ D & A XX SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 361' CEMENTED WITH 225 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD XX POOR _____ CASING LEAK _____ JUNK-IN-HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Circulate heavy mud in hole. 1st plug

@2670'-20 sx. 2nd plug @1680'-100 sx. 3rd plug @410'-40 sx. 4th plug @40' with wiper plug

w/10 sx. Rathole-15 sx. All cement 60/40 posmix, 6% gel.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACC-1 FILED? No
(If not, explain) Sent to operator for completion

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN at:3:00 a.m. on 1-01-89

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS _____

Harold Maley PHONE # (913) 674-5768

ADDRESS 216 E. McFarland, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Jack K. Wharton
(Operator or Agent)

DATE 1-12-89

RECEIVED
STATE CORPORATION COMMISSION
JAN 17 1989
01-17-89
CONSERVATION DIVISION
Wichita, Kansas