

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

15-193-20384-0000

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-193-20,384 (of this well) 6/87
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR TXO Production Corp. OPERATORS LICENSE NO. 5171

ADDRESS 155 N. Market, Suite 1000, Wichita, KS. 67202 PHONE # (316) 269-7600

LEASE (FARM) MEERIAN WELL NO. #1 WELL LOCATION C SE NW 3300' FNL & 3300' FSL COUNTY Thomas

SEC. 34 TWP. 10S RGE. 31 NE 1/4 (W) TOTAL DEPTH 4610' PLUG BACK TD 4350'

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8" SET AT 346' CEMENTED WITH 250 SACKS

CASING SIZE 5-1/2" SET AT 4608' CEMENTED WITH 225 SACKS

PERFORATED AT 4380-89' D.V. Tool @ 2500', cmt w/ 540 sxs Lite cement. Circulate to surface.

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Plug perfs w/ 10 sxs. Fill casing w/ mud to 350'. Dump 10 sxs cement. Fill casing w/ mud to 70', dump 5 sxs cement. Cut off production and surface casing.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? _____ IS ACO-1 FILED? YES
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Jerry W. Collins PHONE # (316) 886-5605

ADDRESS P.O. Box 125-B, R.R. #1, Medicine Lodge, KS. 67104

PLUGGING CONTRACTOR Clarke Oilfield Services LICENSE NO. 5105 6/87

ADDRESS 107 W. Fowler, Medicine Lodge, KS. 67104 PHONE # (316) 886-5665

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Cory West

STATE CORPORATION COMMISSION (Operator or Agent)
Cory West/Drlg & Prod Engineer

4-21-87
APR 20 1987 April 16, 1987



Mike Hayden
Michael Lennen
Margalee Wright
Keith R. Henley
Judith A. McConnell
Brian J. Moline

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286
Ph. 316-263-3238

THIS NOTICE

JUL 24 '87

April 24, 1987

WELL PLUGGING NOTICE

EXPIRES

Meerian #1 3300^{FSL} 3300^{FEL}
~~1980^{FSL} 1980^{FEL}~~
Sec. 34-10S-31W
Thomas County

TXO Production Corporation
155 N. Market, Ste. 1000
Wichita, KS 67202

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

Jack McCord, Director

Please contact the district office to review your suggested method of plugging

DIST. #6 2501 E. 13th, Hays, KS 67601 (913) 628-1200

five days prior to plugging the well (KAR-82-3-113).