

15-193-20329-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-193-20,329 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Energy Exploration, Inc. OPERATORS LICENSE NO. 5063

ADDRESS 1002 So..Broadway, Wichita, KS 67211 PHONE # (316) 267-7336

LEASE (FARM) Hansen WELL NO. 1 WELL LOCATION N/2 NW NW COUNTY Thomas

SEC. 16 TWP. 10S RGE. 33W (E) or (W) TOTAL DEPTH 4750' PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A XXX SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 383' CEMENTED WITH 270 SACKS

CASING SIZE -- SET AT -- CEMENTED WITH -- SACKS

PERFORATED AT - - - -

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 2700' w/30 sx., 390' w/60 sx. 40' Solid

Bridge w/10 sx. 10 sx. in Rathole. 10 sx. in Mousehole. 50-50 pozmix, 6% gel,

3% c.c. 1 sx. Flocel

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? NO
(If not, explain)

Sent to operator for completion

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 4:00 a.m., 11/17/84

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

RECEIVED
STATE CORPORATION COMMISSION

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: 11-26-84
NOV 26 1984

W.W Towns (Toolpusher) PHONE # (913) 462-2423

CONSERVATION DIVISION
Wichita, Kansas

ADDRESS R.R #2, Box 1159, Colby, KS 67701

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 801 Union Center, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Jack L. Partridge

(Operator or Agent)
Jack L. Partridge, Vice Pres.

DATE: November 20, 1984