

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

ORIGINAL

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Operator: License # 33741
Name: Energex Kansas, Inc.
Address: 7300 W. 110th Street, 7th floor
City/State/Zip: Overland Park, KS 66210
Purchaser: Plains Marketing
Operator Contact Person: Phil Frick
Phone: (913) 693-4607
Contractor: Name: Kimzey Drilling
License: 33030

Wellsite Geologist: _____
Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back _____ Plug Back Total Depth _____
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Enhr.?) Docket No. _____

<u>4/23/07</u>	<u>4/24/07</u>	<u>6/1/07</u>
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 107-23846-0000
County: Linn
SW SE NE NW Sec. 30 Twp. 20 S. R. 22 East West
4085 feet from S / N (circle one) Line of Section
3000 feet from E / W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name: Brownrigg Well #: 26
Field Name: Goodrich-Parker


Producing Formation: Squirrel
Elevation: Ground: 928 est. Kelly Bushing: N/A
Total Depth: 612' Plug Back Total Depth: 598.5'
Amount of Surface Pipe Set and Cemented at 20.6 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from 598.5'
feet depth to surface w/ 75 sx cmt.
A142-Dlg - 7/14/08

Drilling Fluid Management Plan
(Data must be collected from the Reserve Pit)
Chloride content _____ ppm Fluid volume _____ bbls
Dewatering method used _____
Location of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Phil Frick
Title: Compliance Coordinator Date: 1/16/08
Subscribed and sworn to before me this 16th day of January,
2008.
Notary Public: Marcia Littell
Date Commission Expires: 3/3/2010



KCC Office Use ONLY

Letter of Confidentiality Received
 If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 17 2008
CONSERVATION DIVISION
WICHITA, KS

Operator Name: Energex Kansas, Inc. Lease Name: Brownrigg Well #: 26
 Sec. 30 Twp. 20 S. R. 22 East West County: Linn

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <i>(Attach Additional Sheets)</i> Samples Sent to Geological Survey <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Submit Copy)</i> List All E. Logs Run: Gamma Ray/Neutron/CCL (Midwest Surveys)	<input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input type="checkbox"/> Sample Name Top Datum Squirrel 548 +380 GL
--	--

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	9 7/8"	7"	17#	20.6'	Portland	8	N/A
Longstring	5 5/8"	2 7/8"	7#	598.5'	Portland	75	N/A

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	548' - 558'		

RECEIVED
 KANSAS CORPORATION COMMISSION
JAN 17 2008
 CONSERVATION DIVISION
 WICHITA, KS

TUBING RECORD		Size	Set At	Packer At	Liner Run <input type="checkbox"/> Yes <input type="checkbox"/> No
Date of First, Resumerd Production, SWD or Enhr.		Producing Method <input type="checkbox"/> Flowing <input type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)			
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity

Disposition of Gas Vented Sold Used on Lease *(If vented, Submit ACO-18.)*

METHOD OF COMPLETION Open Hole Perf. Dually Comp. Commingled Other (Specify) _____

Production Interval _____

Drillers Log

Jay J. Copy

Company J & J Operating LLC
 Farm Brownriggs
 Well No. 26
 API 15-007-23846-0000
 Surface Pipe 20.6" - 7"

County Linn
 Sec 30 Twp 20 Range 22
 Location 4,290' FSL
 Location 2,145' FWL
 Spot W2 SE, NE, NW

T.D. Hole 612' T.D. Pipe 2 7/8 598.50'

Contractor EK Energy LLC

Thickness	Formation	Depth	Remarks
	Soil & Clay	8	Drilled 9 7/8 Hole Set 20.6-7" Cemented
10	Shale	18	
7	Lime	25	5 5/8 Hole
15	Shale	40	
10	Lime	50	Start - 4-23-07 Finish - 4-24-07
6	Shale	56	
91	Lime	147	Core Sample 526'-546'
162	Shale	309	
2	Lime	311	
13	Shale	324	
13	Lime	337	
52	Shale	389	
18	Lime	407	
9	Shale	416	
4	Lime	420	
28	Shale	448	
5	Lime	453	
18	Shale	471	
6	Lime	477	
2	Shale	479	
1	Coal	480	
13	Shale	493	
5	Lime	498	
22	Shale	520	
4	Broken Sand	524	
24	Oil Sand	548	
8	Sandy Shale	556	
2	Oil Sand	558	
6	Sandy Shale	564	
6	Oil Sand	570	
3	Shale	573	
1	Coal	584	
	Shale	T.D.	

RECEIVED
KANSAS CORPORATION COMMISSION


JAN 17 2008

CONSERVATION DIVISION
WICHITA, KS



Owens Oil Co.

1560 2400 St
Iola, Kansas 66749
(316) 365-3455



Invoice No 2372

Date 4-30-07

Sold To

J & J Operating
Brownrig # 26

Sold By

Pulling Unit

Winch Truck

Pump Truck

Service Truck

Quantity

Hrs.

Description

Price

Amount

Cement 2 7/8 in well

600.00

75 sks portland

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 17 2008

CONSERVATION DIVISION
WICHITA, KS