

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

ORIGINAL

Form ACO-1  
September 1999  
Form Must Be Typed

WELL COMPLETION FORM  
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Operator: License # 32432  
Name: LaVeta Oil & Gas LLC  
Address: P.O. Box 780  
City/State/Zip: Middleburg, VA 20118-0780  
Purchaser: Plains  
Operator Contact Person: Bennie C. Griffin  
Phone: (620) 458-9222  
Contractor: Name: Petromark Drilling LLC  
License: 33323  
Wellsite Geologist: Bruce Reed

Designate Type of Completion:  
 New Well  Re-Entry  Workover  
 Oil  SWD  SLOW  Temp. Abd.  
 Gas  ENHR  SIGW  
 Dry  Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:  
Operator: \_\_\_\_\_  
Well Name: \_\_\_\_\_

Original Comp. Date: \_\_\_\_\_ Original Total Depth: \_\_\_\_\_  
 Deepening  Re-perf.  Conv. to Enhr./SWD  
 Plug Back \_\_\_\_\_ Plug Back Total Depth \_\_\_\_\_  
 Commingled \_\_\_\_\_ Docket No. \_\_\_\_\_  
 Dual Completion \_\_\_\_\_ Docket No. \_\_\_\_\_  
 Other (SWD or Enhr.?) \_\_\_\_\_ Docket No. \_\_\_\_\_

10-10-06	10-17-06	10-25-06
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 185-23392-00-00  
County: Stafford

NW 1/4 \_\_\_\_\_ Sec. 13 Twp. 22 S. R. 12  East  West  
1870' feet from S / (N) (circle one) Line of Section  
1560' feet from E / (W) (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:  
(circle one) NE SE (NW) SW  
Lease Name: Jan Well #: 1  
Field Name: Maxwell

Producing Formation: Arbuckle  
Elevation: Ground: 1841' Kelly Bushing: 1846'  
Total Depth: 3742' Plug Back Total Depth: 3701'  
Amount of Surface Pipe Set and Cemented at 366 Feet  
Multiple Stage Cementing Collar Used?  Yes  No  
If yes, show depth set \_\_\_\_\_ Feet  
If Alternate II completion, cement circulated from \_\_\_\_\_  
feet depth to Alt I - Dig - 10-17/08 sx cmt.

Drilling Fluid Management Plan  
(Data must be collected from the Reserve Pit)  
Chloride content 5500 ppm Fluid volume 500 bbls  
Dewatering method used Haul by truck

Location of fluid disposal if hauled offsite:  
Operator Name: LaVeta Oil & Gas LLC  
Lease Name: Komarek #22 License No.: 32432  
Quarter SE 1/4 Sec. 30 Twp. 22 S. R. 11  East  West  
County: Stafford Docket No.: E-27034

**INSTRUCTIONS:** An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Bennie C. Griffin  
Title: Contact Person Date: Dec 21-2006  
Subscribed and sworn to before me this 21 day of December  
20 06  
Notary Public: Glenda Hernandez  
Date Commission Expires: 6-11-2010

**KCC Office Use ONLY**

Letter of Confidentiality Received  
If Denied, Yes  Date: \_\_\_\_\_  
 Wireline Log Received  
 Geologist Report Received  
 UIC Distribution

**RECEIVED**  
KANSAS CORPORATION COMMISSION  
**DEC 26 2006**

GLEND A HERNANDEZ  
NOTARY PUBLIC  
STATE OF KANSAS  
My Appt. Exp. 6-11-2010

CONSERVATION DIVISION  
WICHITA, KS



# ALLIED CEMENTING CO., INC.

24094

PO BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

Great Bend KS

DATE <u>11-2-06</u>	SEC. <u>13</u>	TWP. <u>22S</u>	RANGE <u>12W</u>	CALLED OUT <u>11:30 AM</u>	ON LOCATION <u>7:00 PM</u>	JOB START <u>3:30 PM</u>	JOB FINISH <u>4:00 PM</u>
LEASE <u>Jan</u>	WELL# <u>1</u>	LOCATION <u>TK &amp; Jos, 1 1/2 S</u>			COUNTY <u>STAFFORD</u>	STATE <u>KS</u>	
OLD OR NEW (Circle one) <u>NEW</u>			E.L.O.T.O.				

CONTRACTOR Prtform K # 2  
 TYPE OF JOB Surface  
 HOLE SIZE 12 1/4 TD 380  
 CASING SIZE 8 5/8 DEPTH 360  
 TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 DRILL PIPE 4 1/2 DEPTH 380  
 TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_  
 PRES. MAX 200 PSI MINIMUM \_\_\_\_\_  
 MEAS. LINE \_\_\_\_\_ SHOE JOINT 15 FT  
 CEMENT LEFT IN CSG. 15 FT  
 PERFS. \_\_\_\_\_  
 DISPLACEMENT Fresh water 22 BBIS

OWNER LaVeta Oil & Gas  
 CEMENT  
 AMOUNT ORDERED 280sx A + 396cc + 2% Gel

EQUIPMENT  
 PUMP TRUCK CEMENTER David W.  
 # 181 HELPER Rick H.  
 BULK TRUCK  
 # 344 DRIVER Brandon R.  
 BULK TRUCK  
 # \_\_\_\_\_ DRIVER \_\_\_\_\_

COMMON 280sx @ 10.65 2982.00  
 POZMIX \_\_\_\_\_ @ \_\_\_\_\_ \_\_\_\_\_  
 GEL 5 gal @ 16.46 82.25  
 CHLORIDE 3 gal @ 46.00 138.00  
 ASC \_\_\_\_\_ @ \_\_\_\_\_ \_\_\_\_\_

RECEIVED  
 KANSAS CORPORATION COMMISSION  
 OCT 16 2008  
 CONSERVATION DIVISION  
 WICHITA, KS

HANDLING 293 gal @ 1.90 556.70  
 MILEAGE 293.2409 @ 24 632.88  
 TOTAL 4627.63

REMARKS:

PPC on Bottom Break CIRC Pump  
 280sx A + 396cc + 2% Gel  
 shut Down Release Plug  
 Displace w/ BBIS Fresh  
 Water shut in cement did  
 CIRC wash up Rig Down.

SERVICE

DEPTH OF JOB 360 FT  
 PUMP TRUCK CHARGE \_\_\_\_\_ 815.00  
 EXTRA FOOTAGE 66 @ 6.25 412.50  
 MILEAGE 24 @ 6.00 144.00  
 MANIFOLD ~~\_\_\_\_\_~~ @ \_\_\_\_\_ \_\_\_\_\_

TOTAL 1001.90

CHARGE TO: LaVeta Oil & Gas  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

PLUG & FLOAT EQUIPMENT

1-Warden Plug @ 60.00 60.00  
 \_\_\_\_\_ @ \_\_\_\_\_ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_ \_\_\_\_\_  
 \_\_\_\_\_ @ \_\_\_\_\_ \_\_\_\_\_  
 TOTAL 60.00

To Allied Cementing Co., Inc.  
 You are hereby requested to rent cementing equipment and furnish cement and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_  
 TOTAL CHARGE \_\_\_\_\_  
 DISCOUNT \_\_\_\_\_ IF PAID IN 30 DAYS

SIGNATURE [Signature]

[Signature]  
 PRINTED NAME



**SALES OFFICE:**  
 100 S. Main  
 Suite #607  
 Wichita, Ks. 67202  
 316-262-3699  
 316-262-5799 FAX

**SALES & SERVICE OFFICE:**  
 10244 NE. Hwy 61  
 P.O. Box 8613  
 Pratt, Ks. 67124-8613  
 620-672-1201  
 620-672-5383 FAX

**SALES & SERVICE OFFICE:**  
 1700 S. Country Estates Rd.  
 P.O. Box 129  
 Liberal, Ks. 67905-0129  
 620-624-2277  
 620-624-2280 FAX

**Invoice** ✓

**Bill to:** 5708610  
 LA VETA OIL & GAS L.L.C  
 P.O. Box 780  
 Middleburg, VA 20118-0780

**Customer Rep**  
 Bennie

Invoice	Invoice Date	Order	Station
611075	11/10/06	15379	Pratt
Service Description			
Cement			
Lease	Well	Well Type	
Jan	1	New Well	
AFE	PO	Terms	
		Net 30	
Treater			
Bobby Drake			

ID.	Description	UOM	Quantity	Unit Price	Price
D205	AA2 (COMMON)	SK	150	\$15.90	\$2,385.00 (T)
D203	60/40 POZ (COMMON)	SK	15	\$10.30	\$154.50 (T)
C221	SALT (Fine)	GAL	704	\$0.25	\$176.00 (T)
C243	DEFOAMER	LB	36	\$3.45	\$124.20 (T)
C244	CEMENT FRICTION REDUCER	LB	43	\$6.00	\$258.00 (T)
C312	GAS BLOCK	LB	106	\$5.15	\$545.90 (T)
C321	GILSONITE	LB	751	\$0.67	\$503.17 (T)
C302	MUD FLUSH	GAL	500	\$0.86	\$430.00 (T)
F211	AUTO FILL FLOAT SHOE, 5 1/2"	EA	1	\$320.00	\$320.00 (T)
F171	LATCH DOWN PLUG & BAFFLE, 5 1/2"	EA	1	\$250.00	\$250.00 (T)
F121	BASKET, 5 1/2"	EA	1	\$237.50	\$237.50 (T)
F101	TURBOLIZER, 5 1/2"	EA	6	\$74.20	\$445.20 (T)
F291	CEMENT SCRATCHERS CABLE TYPE, 5 1/2"	EA	25	\$60.00	\$1,500.00 (T)
E100	HEAVY VEHICLE MILEAGE - 1 WAY	MI	90	\$5.00	\$450.00
E101	CAR, PICKUP OR VAN MILEAGE - 1 WAY	MI	45	\$3.00	\$135.00
E104	PROPPANT / BULK DELIV SERVICES/TON MILE, \$200 MIN	TM	347	\$1.60	\$555.20
E107	CEMENT SERVICE CHARGE	SK	165	\$1.50	\$247.50
R208	CASING CEMENT PUMPER, 3501-4000' 1ST 4 HRS ON LOC	EA	1	\$1,680.00	\$1,680.00
R701	CEMENT HEAD RENTAL	EA	1	\$250.00	\$250.00
R702	CASING SWIVEL RENTAL	EA	1	\$150.00	\$150.00
R404	DERRICK CHARGE, ABOVE 10'	EA	1	\$250.00	\$250.00

RECEIVED  
 KANSAS CORPORATION CO-MISSION  
 OCT 16 2008  
 CONSERVATION DIVISION  
 WICHITA, KS

**Sub Total:** \$11,047.17  
**Discount:** \$1,326.36  
**Discount Sub Total:** \$9,720.81  
**Stafford County & State Tax Rate: 6.30%** **Taxes:** \$406.32  
**(T) Taxable Item Total:** \$10,127.13

**PLEASE REMIT TO Acid Services, LLC, Dept No 1131, Tulsa, OK, 74182**

Accounts are past due not 30 days following the date of invoice. Finance charge of 1 1/2% per month or 18% annual percentage rate will be charged on all past due accounts. Customer agrees not to withhold payment of any invoice, or assert any right of offset, recoupment or any other defense to payment of any invoice, on account of any right that you may now or hereafter have to payment from us, except for claims arising out of such invoice because of defects in the specific services described in such invoice. Additionally, you hereby waive any right that you may have under any state, federal or other law to assert



**FIELD ORDER** 15379

Subject to Correction

Lease	Jan	Well #	1	Legal	13-22s-12w
County	Stafford	State	Ks.	Station	Pratt
Depth		Formation	3741'	Shoe Joint	42'
Casing	5 1/2"	Casing Depth	2059'	TD	3940'
Customer Representative	Denise	Treater	Bobby Drake	Job Type	5 1/2 L.S. N.W.

AFE Number	PO Number	Materials Received by	X Ben C. Dyer
------------	-----------	-----------------------	---------------

Station Code	Product Code	QUANTITY	MATERIALS, EQUIPMENT, and SERVICES USED	UNIT PRICE	AMOUNT
P	D205	152sk.	AA2	-	
P	D203	15sk.	60/40.8oz	-	
P	C221	724lb.	Salt (Fine)	-	
P	C243	36lb.	Defoamer	-	
P	C244	43lb.	Corrosion Fraction Reducer	-	
P	C312	106lb.	Gas Block	-	
P	C321	751lb.	Gilsonite	-	
P	C302	500gal.	Mud Flush	-	
P	F211	1ea.	Auto Fill Float Valve, 5 1/2"	-	
P	F2171	1ea.	I.R. Latch Down Plug & Baffle, 5 1/2"	-	
P	F121	1ea.	Basket, 5 1/2"	-	
P	F121	1ea.	Turner Valve, 5 1/2"	-	
P	F291	25ea.	Corrosion Inhibitor Cable Type, 5 1/2"	-	
P	E100	2Days	Heavy Vehicle Mileage		
P	E101	45mi.	Pick up Mileage		
P	E104	347mi.	Bulk Delivery		
P	E107	165sk.	Corrosion Service Charge		
P	R208	1ea.	Corrosion Pump 3501-4000'		
P	L701	1ea.	Corrosion Head Rental		
P	L702	1ea.	Corrosion Sump Rental		
P	L702	1ea.	Drill Rig Charge		

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 16 2008  
CONSERVATION DIVISION  
WICHITA, KS

Discounted Price - \$9120.81

**TOTAL**