

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION

Form ACO-1  
September 1999  
Form Must Be Typed

WELL COMPLETION FORM  
WELL HISTORY - DESCRIPTION OF WELL & LEASE

ORIGINAL

Operator: License # 5093  
Name: Victor J. Leis  
Address: Box 223  
City/State/Zip: Yates Center, KS 66763  
Purchaser: C.M.T.  
Operator Contact Person: Victor J. Leis  
Phone: (913) 294-4033  
Contractor: Name: John E. Lois  
License: 32079  
Wellsite Geologist: n/a

Designate Type of Completion:  
 New Well  Re-Entry  Workover  
 Oil  SWD  SLOW  Temp. Abd.  
 Gas  ENHR  SIGW  
 Dry  Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:  
Operator: n/a

Well Name: \_\_\_\_\_  
Original Comp. Date: \_\_\_\_\_ Original Total Depth: \_\_\_\_\_  
 Deepening  Re-perf.  Conv. to Enhr./SWD  
 Plug Back \_\_\_\_\_ Plug Back Total Depth \_\_\_\_\_  
 Commingled \_\_\_\_\_ Docket No. \_\_\_\_\_  
 Dual Completion \_\_\_\_\_ Docket No. \_\_\_\_\_  
 Other (SWD or Enhr.?) \_\_\_\_\_ Docket No. \_\_\_\_\_

|                                   |                  |   |
|-----------------------------------|------------------|---|
| <u>4/9/2006</u>                   | <u>4/12/2006</u> | <u>5/20/2006</u>                        |
| Spud Date or<br>Recompletion Date | Date Reached TD  | Completion Date or<br>Recompletion Date |

API No. 15 207-27008-00-00  
County: Woodson  
NF  SW  NE  NW Sec. 4 Twp. 24 S. R. 15  East  West  
895 895 feet from S /  (circle one) Line of Section  
1910 1910 feet from E /  (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:  
(circle one) NE SE  NW SW  
Lease Name: Tannahill Well #: 33

Field Name: Vernon  
Producing Formation: Squirrel  
Elevation: Ground: n/a Kelly Bushing: n/a  
Total Depth: 1103' Plug Back Total Depth: n/a  
Amount of Surface Pipe Set and Cemented at 40 Feet  
Multiple Stage Cementing Collar Used?  Yes  No  
If yes, show depth set n/a Feet  
If Alternate II completion, cement circulated from 1106'  
feet depth to surface w/ 95 sx cmt.

Drilling Fluid Management Plan A17 II NH 7-11-08  
(Data must be collected from the Reserve Pit)  
Chloride content n/a ppm Fluid volume n/a bbls  
Dewatering method used n/a  
Location of fluid disposal if hauled offsite:  
Operator Name: n/a  
Lease Name: \_\_\_\_\_ License No.: \_\_\_\_\_  
Quarter \_\_\_\_\_ Sec. \_\_\_\_\_ Twp. \_\_\_\_\_ S. R. \_\_\_\_\_  East  West  
County: \_\_\_\_\_ Docket No.: \_\_\_\_\_

**INSTRUCTIONS:** An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Victor J. Leis  
Title: Owner Date: 6-21-07  
Subscribed and sworn to before me this 21<sup>st</sup> day of June, 2007.  
Notary Public: Judith A. Smith  
Date Commission Expires: 10-18-08

JUDITH A. SMITH  
Notary Public - State of Kansas  
My Appt. Expires 10-18-08

**KCC Office Use ONLY**

Letter of Confidentiality Received  
 If Denied, Yes  Date: \_\_\_\_\_  
 Wireline Log Received  
 Geologist Report Received  
 UIC Distribution

**RECEIVED**  
KANSAS CORPORATION COMMISSION  
**JUN 28 2007**



# LEIS OIL SERVICES

111 East Mary • Yates Center, Kansas 66783 • (620) 625-3676

|   |                                      |
|---|--------------------------------------|
| Operator License #: 5983                  | API: 207-26934                       |
| Operator: Victor J. Leis Drilling Company | Lease Name: Tannahill                |
| Address: PO Box 223, Yates Center, KS     | Well #: 33                           |
| Phone #: 913.294.4833                     | Spud Date: 4.9.06 Completed: 4.12.06 |
| Contractor License #: 32079               | Location: NE-SWNE-NW of 4.24.16E     |
| T.D.: 1108 T.D. of Pipe: 1104             | 895 Ft from North Line               |
| Surface Pipe Size: 7" Depth: 40'          | 1910 Ft from East Line               |
| Kind of Well (Oil, Gas, Water, Dry): Oil  | County: Woodson                      |

## LOG

| Thickness | Strata        | From | To  | Thickness | Strata         | From | To   |
|-----------|---------------|------|-----|-----------|----------------|------|------|
| 10        | Clay and Soil | 0    | 10  | 12        | Sandy Shale    | 968  | 980  |
| 3         | Lime          | 10   | 13  | 4         | Shale          | 980  | 984  |
| 27        | Sandy Shale   | 13   | 40  | 6         | Lime           | 984  | 990  |
| 147       | Shale         | 40   | 187 | 3         | Black Shale    | 990  | 993  |
| 5         | Lime          | 187  | 192 | 4         | Lime           | 993  | 997  |
| 8         | Shale         | 192  | 200 | 4         | White Shale    | 997  | 1001 |
| 60        | Shale         | 200  | 260 | 3         | Sandy Shale    | 1001 | 1004 |
| 4         | Red Shale     | 260  | 264 | 2         | Light Oil Sand | 1004 | 1006 |
| 11        | Shale         | 264  | 275 | 37        | Sandy Shale    | 1006 | 1043 |
| 135       | Lime          | 275  | 410 | 1         | Cap Rock       | 1043 | 1044 |
| 48        | Chalky Lime   | 410  | 458 | 2         | Oil Show       | 1044 | 1046 |
| 147       | Lime          | 458  | 605 | 2         | Good Show      | 1046 | 1048 |
| 3         | Black Shale   | 605  | 608 | 3         | Good Show      | 1048 | 1051 |
| 24        | Lime          | 608  | 632 | 2         | Light Show     | 1051 | 1053 |
| 3         | Black Shale   | 632  | 635 | 55        | Sandy Shale    | 1053 | 1108 |
| 22        | Lime          | 635  | 657 |           |                |      |      |
| 137       | Big Shale     | 657  | 794 |           |                |      |      |
| 29        | Sandy Shale   | 794  | 823 |           |                |      |      |
| 25        | Sandy Lime    | 823  | 848 |           |                |      |      |
| 18        | Hard Lime     | 848  | 866 |           |                |      |      |
| 49        | Sandy Shale   | 866  | 915 |           |                |      |      |
| 12        | Lime          | 915  | 927 |           |                |      |      |
| 14        | Sandy Shale   | 927  | 941 |           | T.D.           |      | 1108 |
| 5         | Lime          | 941  | 946 |           | T.D. of pipe   |      | 1104 |
| 16        | Sandy Lime    | 946  | 962 |           |                |      |      |
| 6         | Lime          | 962  | 968 |           |                |      |      |

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 28 2007

CONSERVATION DIVISION  
WOODSON COUNTY

CONSOLIDATED OIL WELL SERVICES, INC.  
11 W. 14TH STREET, CHANUTE, KS 66720  
20-431-9210 OR 800-467-8676

TICKET NUMBER 4152  
LOCATION Oftawa KS  
FOREMAN Fred Mead

TREATMENT REPORT & FIELD TICKET  
CEMENT

| DATE            | CUSTOMER # | WELL NAME & NUMBER | SECTION                     | TOWNSHIP | RANGE             | COUNTY |
|-----------------|------------|--------------------|-----------------------------|----------|-------------------|--------|
| 4-12-06         | 5353       | Tannahill #33      | 32                          | 23       | 16                | WA     |
| CUSTOMER        |            |                    | TRUCK #                     | DRIVER   | TRUCK #           | DRIVER |
| MAILING ADDRESS |            |                    | 372                         | Fred     | 489-7102 (Thayer) |        |
| P.O. Box 1000   |            |                    | 290                         | Rick     | George Taylor     |        |
| CITY            |            |                    | 144                         | Mark     |                   |        |
| STATE           |            |                    | 441 - (Eureka - Steve Mead) |          |                   |        |
| ZIP CODE        |            |                    |                             |          |                   |        |
| Miami OK 74354  |            |                    |                             |          |                   |        |

JOB TYPE Long string HOLE SIZE 5 1/4 HOLE DEPTH 1108 CASING SIZE & WEIGHT 2 3/8 EOE  
 CASING DEPTH 1102 DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
 SLURRY WEIGHT \_\_\_\_\_ SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING 2 1/2 rubber Plug  
 DISPLACEMENT 6.4 BBL DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE 3 BPM

REMARKS: Establish Circulation. Mix + Pump 200# Premium Gel  
Flush. Mix + Pump 65 sks 50/50 Poz Mix Cement  
w/ 6% Gel - Follow with 30 sks owc Cement.  
Flush pump + lines clean. Displace 2 1/2 rubber  
plug to casing TD with 6.4 BBLs Fresh water  
Pressure to 600# PSI Shut in casing

Fred Mead

John Heis Drilling

| ACCOUNT CODE    | QUANTITY or UNITS | DESCRIPTION of SERVICES or PRODUCT | UNIT PRICE | TOTAL   |
|-----------------|-------------------|------------------------------------|------------|---------|
| 5401            | 1                 | PUMP CHARGE Cement Pump            | 290        | 800.00  |
| 5406            | 55 mi             | MILEAGE Pump Truck                 | 290        | 173.25  |
| 5407            | Minimum           | Tan Mileage                        | 144        | 275.00  |
| 5407.35         | Minimum           | Tan Mileage (Eureka)               | 441        | 275.00  |
| 5501 C.10       | 4 hrs             | Transport (Thayer)                 | 489-7103   | 392.00  |
| 1124.35         | 61 sks            | 50/50 Poz Mix Cement               |            | 539.85  |
| 1118 A.35       | 328#              | S-5 Gel Bentonite                  |            | 45.92   |
| 1126            | 30 sks            | owc Cement                         |            | 439.50  |
| 1118 B          | 200#              | Premium Gel                        |            | 28.00   |
| 4402            | 1                 | 2 1/2" rubber Plug                 |            | 18.00   |
| Sub Total       |                   |                                    |            | 4057.27 |
| Wot# 204675     |                   |                                    |            | 67.48   |
| 204676          |                   |                                    |            |         |
| 204677          |                   |                                    |            |         |
| SALES TAX       |                   |                                    |            |         |
| ESTIMATED TOTAL |                   |                                    |            | 3054.00 |