

CONFIDENTIAL

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

ORIGINAL

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Operator: License # 32309
Name: Presco Western, LLC
Address: 5480 Valmont, Ste. 350
City/State/Zip: Boulder, CO 80301
Purchaser: Plains Marketing LP - Oil OneOK - Gas
Operator Contact Person: Leonard Witkowski
Phone: (303) 444-8881
Contractor: Name: Murfin
License: 30606
Wellsite Geologist: Boulder office

KCC

SEP 25 2006

CONFIDENTIAL

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____

Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back Plug Back Total Depth
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Enhr.?) Docket No. _____

<u>6/28/2006</u>	<u>7/8/2006</u>	<u>8/3/2006</u>
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 081-21665-00-00
County: Haskell
NE NW NE SE SW SW Sec. 15 Twp. 30 S. R. 32 East West
330 feet from S N (circle one) Line of Section
1895 feet from E W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name: Diaden Farms Well #: 5-B15-30-32
Field Name: Unnamed

Producing Formation: Morrow
Elevation: Ground: 2879 Kelly Bushing: 2890
Total Depth: 5672 Plug Back Total Depth: _____
Amount of Surface Pipe Set and Cemented at 1685 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set Port Collar 3158 Feet
If Alternate II completion, cement circulated from _____
feet depth to _____ w/ _____ sx cmt.

Drilling Fluid Management Plan
(Data must be collected from the Reserve Pit)
Chloride content 6000 ppm Fluid volume 1800 bbls
Dewatering method used Air Evaporation
Location of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: _____

ALT I with
9-25-06

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: _____
Title: Regulatory Specialist Date: 9/25/2006

Subscribed and sworn to before me this 25 day of September,
2006.

Notary Public: _____
Date Commission Expires: 4-7-09

JENNIFER THOMAS
Notary Public
State of Colorado

KCC Office Use ONLY

4 Letter of Confidentiality Received
If Denied, Yes Date: _____
Wireline Log Received
Geologist Report Received
UIC Distribution

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 26 2006
CONSERVATION DIVISION
WICHITA, KS

TIG

Operator Name: Presco Western, LLC Lease Name: Diaden Farms Well #: 5-B15-30-32
 Sec. 15 Twp. 30 S. R. 32 East West County: Haskell

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken Yes No
 (Attach Additional Sheets)

Samples Sent to Geological Survey Yes No

Cores Taken Yes No

Electric Log Run Yes No
 (Submit Copy)

List All E. Logs Run:

Compensated Neutron Density Log/SSD Log; Dual Induction; Borehole Compensated Sonic w/ITT Log

Log Formation (Top), Depth and Datum Sample

Name	Top	Datum
Heebner	4145	-1255
Lansing	4210	-1320
Kansas City	4685	-1795
Marmaton	4850	-1960
Pawnee	4950	-2060
Ft Scott	4985	-2095
Morrow	5270	-2380
St Genevieve	5470	-2580

CASING RECORD New Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12-1/4"	8-5/8"	23	1690	Comm/Lite	150/575	3%CC, Lite, 3%CC, 1/4#floseal
Production	7-7/8"	5-1/2"	15.5	5672	ASC	200	2% gel, 10% sst, 5# gll, .5%FL160
Port Collar		5-1/2"	15.5	3158	Lite	450	Lite, 1/4# FL160

ADDITIONAL CEMENTING / SQUEEZE RECORD

Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
4	5314-5330	2000g 15%NEFE; 50 bbls 2% flush	

RECEIVED
 KANSAS CORPORATION COMMISSION
 SEP 26 2006
 CONSERVATION DIVISION
 WICHITA, KS

TUBING RECORD Size 2-7/8 Set At 5630 Packer At _____ Liner Run Yes No

Date of First, Resumerd Production, SWD or Enhr. 8/5/2006 Producing Method Flowing Pumping Gas Lift Other (Explain)

Estimated Production Per 24 Hours
 Oil Bbls. 0 Gas Mcf 267 Water Bbls. 0 Gas-Oil Ratio 99999 Gravity 37.5

Disposition of Gas _____ METHOD OF COMPLETION _____ Production Interval _____

Vented Sold Used on Lease Open Hole Perf. Dually Comp. Commingled
 (If vented, Submit ACO-18.) Other (Specify) _____

T1647

ALLIED CEMENTING CO., INC. 24664

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Oakley

DATE <u>1/30/06</u>	SEC. <u>15</u>	TWP. <u>30s</u>	RANGE <u>32W</u>	CALLED OUT	ON LOCATION <u>1:00 PM</u>	JOB START <u>1:30 PM</u>	JOB FINISH <u>4:45 PM</u>
LEASE <u>Diadel Farms</u>				WELL # <u>5-0-15-20-21</u>	LOCATION <u>83+56 Jet 3E 2s 34E S/S</u>	COUNTY <u>Haskell</u>	STATE <u>KS</u>
OLD OR <u>NEW</u> (Circle one)							

CONTRACTOR Max Fin #21

TYPE OF JOB Cmt 8 3/4 CSG

HOLE SIZE 12 1/4 T.D. 1685 1700

CASING SIZE 8 3/8 23# DEPTH 1685 1700

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX 1800 MINIMUM 100

MEAS. LINE SHOE JOINT 40

CEMENT LEFT IN CSG 40

PERFS.

DISPLACEMENT 10 sks

OWNER Same

CEMENT AMOUNT ORDERED

575 sks Lite weight + 300 lb 4 1/2 Seal

150 sks com + 300 lb

COMMON	<u>150 sks</u>	@ <u>12.20</u>	<u>1830.00</u>
POZMIX		@	
GEL	<u>30 sks</u>	@ <u>16.65</u>	<u>499.50</u>
CHLORIDE	<u>24 sks</u>	@ <u>46.60</u>	<u>1118.40</u>
ASC		@	
<u>Lite weight</u>	<u>575 sks</u>	@ <u>11.30</u>	<u>6497.50</u>
<u>Flo-seal</u>	<u>144 #</u>	@ <u>2.00</u>	<u>288.00</u>
		@	
		@	
		@	
		@	
		@	
HANDLING	<u>785 sks</u>	@ <u>1.90</u>	<u>1491.50</u>
MILEAGE	<u>88 1/2 mi</u>		<u>2178.00</u>
			TOTAL <u>13922.90</u>

EQUIPMENT

PUMP TRUCK CEMENTER Max

373-291 HELPER Jarrod

BULK TRUCK

396 DRIVER Larry

BULK TRUCK

394 DRIVER Rex

REMARKS:

Pressure csg with truck to 1900 to break circulation. Max 575 sks used. 150 sks Tail Cmt. Drop Plug Displace 10 G. AP. Land. Plug Plant Head cement. Did Circulate

SERVICE

DEPTH OF JOB	<u>1685 1700</u>		
PUMP TRUCK CHARGE			<u>1610.00</u>
EXTRA FOOTAGE	@		
MILEAGE	<u>35 mi</u>	@ <u>5.00</u>	<u>175.00</u>
MANIFOLD	@		
<u>Head Rental</u>	@		<u>100.00</u>
	@		
			TOTAL <u>1885.00</u>

CHARGE TO: Presco Western

STREET _____

CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

<u>1-8 3/4 Rubber Plug</u>	@	<u>100.00</u>
<u>1-9 3/4 C-widex Short</u>	@	<u>235.00</u>
<u>1-9 3/4 AEU Insert</u>	@	<u>325.00</u>
<u>4-8 3/4 Centralizers</u>	@ <u>55.00</u>	<u>220.00</u>
1-8 3/4 Centralizer	@	55.00
		TOTAL <u>880.00</u>

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Randy [Signature]

PRINTED NAME Randy [Signature]

KCC
SEP 25 2006
CONFIDENTIAL

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 26 2006
CONSERVATION DIVISION
WICHITA, KS

ALLIED CEMENTING CO., INC. 24437

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Oakley

DATE <u>7-10-06</u>	SEC <u>15</u>	TWP <u>30s</u>	RANGE <u>32W</u>	CALLED OUT	ON LOCATION <u>12:00 PM</u>	JOB START <u>4:45 PM</u>	JOB FINISH <u>5:30 PM</u>
LEASE <u>Digden Farms</u>	WELL # <u>5-B-153032</u>	LOCATION <u>89+56 SW 3E-2s 34E9s</u>			COUNTY <u>Haskell</u>	STATE <u>Ks</u>	
OLD OR NEW (Circle one)							

CONTRACTOR Murphy Drly Rig 21
 TYPE OF JOB Production string
 HOLE SIZE 7 1/8" T.D. 5684'
 CASING SIZE 5 1/2" DEPTH 5684'
 TUBING SIZE DEPTH
 DRILL PIPE DEPTH
 TOOL Port collar DEPTH 3098'
 PRES. MAX MINIMUM
 MEAS. LINE SHOE JOINT 21.01'
 CEMENT LEFT IN CSG. 21.01'
 PERFS.
 DISPLACEMENT 134 3/4
 EQUIPMENT

OWNER Same
 CEMENT
 AMOUNT ORDERED 200 sks ASC 271 Gal
1020 salt, 5' Gypsum, 200# FL 160
500 gals WFR-2
 COMMON @
 POZMIX @
 GEL 4 sks @ 16.65 66.60
 CHLORIDE @
 ASC 200 sks @ 14.20 2840.00
5917 24 sks @ 9.60 230.40
Gypsum 1000# @ .70 700.00
FL-160 94 # @ 10.65 1001.10
WFR-2 500 gals @ 1.00 500.00
 @
 @
 @
 @
 @
 @
 HANDLING 271 sks @ 1.90 514.90
 MILEAGE 84 /sk mile 758.80
 TOTAL 6611.80

KCC
SEP 25 2006
CONFIDENTIAL

PUMP TRUCK CEMENTER Dean
 # 373-281 HELPER Andrew
 BULK TRUCK
 # 218 DRIVER Larry
 BULK TRUCK
 # DRIVER

REMARKS:
Plug Rat Hole w/15 sks
Plug mouse hole w/10 sks
pump 500 gals WFR-2 followed with
200 sks cement, wash pump & line
118 Disg. 134 3/4 Bbls. Plug landed.
Float held. Lost circulation last
10 Bbls.
Thank you

SERVICE
 DEPTH OF JOB 5684'
 PUMP TRUCK CHARGE 1965.00
 EXTRA FOOTAGE @
 MILEAGE 35 miles @ 5.00 175.00
 MANIFOLD @
Head Rental @ 100.00
 @
 TOTAL 2240.00

CHARGE TO: Presco Western
 STREET _____
 CITY _____ STATE _____ ZIP _____

1/2 PLUG & FLOAT EQUIPMENT
 Guide shoe 160.00
 (B) AFH Insert @ 250.00
 7-centralizers @ 50.00 350.00
 (B) 1-Basker @ 150.00
 Port collar @ 1750.00
 5/2 Rubber Plug @ 65.00
 TOTAL 2725.00

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

SIGNATURE Rodney Gonzales

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS
 PRINTED NAME Rodney Gonzales

RECEIVED
 KANSAS CORPORATION COMMISSION
 SEP 26 2006
 CONSERVATION DIVISION
 WICHITA, KS

ALLIED CEMENTING CO., INC.

25932

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Oakley

DATE <u>7-28-06</u>	SEC <u>15</u>	TWP. <u>30^S</u>	RANGE <u>32^W</u>	CALLED OUT	ON LOCATION <u>10:00^{PM}</u>	JOB START <u>10:30^{PM}</u>	JOB FINISH <u>11:30^{PM}</u>
LEASE <u>Diadem Farms</u>	WELL # <u>E-5</u>	LOCATION <u>Sublett 1E-2S-1 1/2 E</u>			COUNTY <u>Haskell</u>	STATE <u>Kan</u>	
OLD OR NEW (Circle one) <u>NEW</u>				S/S			

CONTRACTOR E. J. Dredge Well Service

OWNER

TYPE OF JOB Port Celler

HOLE SIZE T.D.

CASING SIZE 5 1/2 DEPTH

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL Port Celler DEPTH 3156'

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT

CEMENT LEFT IN CSG.

PERFS.

DISPLACEMENT 18.1 BBL

EQUIPMENT

PUMP TRUCK # 373 CEMENTER Walt HELPER Andrew

BULK TRUCK # 399 DRIVER Mike

BULK TRUCK # DRIVER

REMARKS:

Test casing to 1500ft open
 Tool & Pump into, had no Blow
 mixed 450 sks cement, have
 CMC then John, cement did not
 cure. Displace 17 1/2 BBL water
 shut tool, test to 1500ft. Held
 run 5 hrs, reversed. Thank You
 out

CEMENT

AMOUNT ORDERED 450 sks Lite
1/4# Flo-Seal KCC

COMMON

POZMIX

GEL

CHLORIDE

ASC

Lite 450 sks @ 10.75 4,837.50
Flo-seal 113# @ 2.00 226.00

HANDLING 476 sks @ 1.90 908.40

MILEAGE 84 per sk @ 16.00 1,338.40

TOTAL 7,310.30

SERVICE

DEPTH OF JOB
PUMP TRUCK CHARGE 9.55 00

EXTRA FOOTAGE @
MILEAGE 35-miles @ 5.00 175.00

MANIFOLD @

TOTAL 1,130.00

CHARGE TO: Presco-Western

STREET

CITY STATE ZIP

RECEIVED PLUG & FLOAT EQUIPMENT
KANSAS CORPORATION COMMISSION

SEP 26 2006

CONSERVATION DIVISION
WICHITA, KS

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment
and furnish cement and labor to assist in