

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21622-00-00
Spot: NESWSE Sec/Twnshp/Rge: 3-30S-7W
810 feet from S Section Line, 1825 feet from E Section Line
Lease Name: H.C. KYLE Well #: 3-3
County: KINGMAN Total Vertical Depth: 4210 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4208	3240	100 SXS CMT
SURF	8.625	289		170 SXS CMT <u>136.83</u>

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 10/07/2008 8:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND PERFS BACK TO 4080' AND CAP WITH 5 SKS CMT. RECOVER CASING. SPOT 35 SKS AT 1100', 35 SKS AT 700', CIRC CMT FROM 340-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE
Date/Time Plugging Completed: 10/07/2008 10:30 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND FROM 4159 TO 4080', AND CAPPED WITH 5 SKS OF CMT. THE CASING WAS RECOVERED FROM 3240', AND PULLED TO 1100', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED 700', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 340', WHERE CMT WAS CIRCD TO SURFACE. CASING PULLED FROM WELLBORE AND CMT WAS TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
4143	4153		
INVOICED DATE <u>12-22-08</u> INV. NO. <u>2009060875</u>			
RECEIVED KANSAS CORPORATION COMMISSION NOV 26 2008 CONSERVATION DIVISION WICHITA, KS			

Remarks: QUALITY OIL WELL CEMENTING #2380 60/40 POZ 4% GEL

Plugged through: CSG

District: 02

Signed [Signature]
(TECHNICIAN)