

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-20597-00-00
Spot: NENESWSW Sec/Twnshp/Rge: 35-23S-33W
1250 feet from S Section Line, 4030 feet from E Section Line
Lease Name: KNOLL Well #: 1
County: FINNEY Total Vertical Depth: 3000 feet

Operator License No.: 32832
Op Name: PETROHAWK OPERATING COMPANY
Address: 1000 LOUISIANA, STE 5600
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2999	0	WITH 400 SX CMT
SURF	8.625	1659		WITH 700 SX CMT <u>97.50</u>

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/03/2008 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: EARL OCHAMPAUGH Company: PETROHAWK OPERATING Phone: (832) 204-2700

Proposed Plugging Method: PER KCC INSTRUCTIONS 400 LBS HULLS, 180 SACKS IN 4 1/2 CASING, 100 SACKS BACKSIDE ANNULUS CEMENT 60-40 POS WITH 4% GEL.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/03/2008 10:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH CMT FROM 2693'-0" USING 400# HULLS AND 185 SX CMT. PRESSURE TO 500#. HOLDING. PUMP 75 SX CMT DOWN 4 1/2" X 8 5/8" ANNULUS. PRESSURE TO 400# & HELD.

Perfs:

Top	Bot	Thru	Comments
2683	2693		
2604	2612		
2568	2578		

INVOICED
DATE 12-22-08
INV. NO. 2009060881

RECEIVED
KANSAS CORPORATION COMMISSION


NOV 24 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed

Ken Jehlik
(TECHNICIAN)