

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

KCC PLET
GPS
nws

API Well Number: 15-047-21107-00-00

Spot: W2SENE

Sec/Twnshp/Rge: 34-25S-16W

3250 ~~3300~~ feet from S Section Line,

~~990~~ feet from E Section Line

Lease Name: GIBSON

1054 Well #: 2-A

County: EDWARDS

Total Vertical Depth: 4484 feet

Operator License No.: 5893

Op Name: PRATT WELL SERVICE, INC.

Address: PO BOX 847
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4483	1320	WITH 175 SX CMT
SURF	8.625	425		WITH 350 SX CMT <u>145.73</u>

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/14/2008 9:30 AM

Plug Co. License No.: 5893

Plug Co. Name: PRATT WELL SERVICE, INC.

Proposal Rcvd. from: GERALD INSLEE

Company: PRATT WELL SERVICE, INC.

Phone: (620) 672-2531

Proposed Plugging Method: SET CIBP @ 4390' WITH 2 SX CMT OR SAND TO 4390' & 4 SX CMT. PLUG AT 1060' WITH 12 SX GEL & 50 SX CMT. PLUG AT 460' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/14/2008 11:15 AM

KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

SAND TO 4260' WITH 4 SX CMT. 1ST PLUG AT 1079' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 473' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4440	4460		


INVOICED
DATE 12-22-08
INV. NO. 2009060882

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 24 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01



Signed

Jerry W Stapleton
(TECHNICIAN)
PRATT

Form SP-2/3