

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21603-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 11-9S-17W
990 feet from S Section Line, 4950 feet from E Section Line
Lease Name: OSWALD Well #: 1
County: ROOKS Total Vertical Depth: 3482 feet

Operator License No.: 30537
Op Name: VENTURE RESOURCES, INC.
Address: PO BOX 101234
DENVER, CO 80250

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3465	0	w/100 sxs cmt
SURF	8.625	217	0	w/140 sxs cmt

113.17

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/10/2008 10:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: JOHN CEARLEY Company: VENTURE RESOURCES, INC. Phone: (303) 722-2899

Proposed Plugging Method: Ordered out 400 sxs 60/40 pozmix - 4% gel - 500# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/10/2008 1:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

No squeeze records - perforated two holes each at 1314' and 775'.
Ran tubing to 2488' - pumped 200 sxs 60/40 pozmix - 4% gel with 300# hulls cwc.
PTOH. Squeezed 55 sxs cement down 4 1/2" casing.
Max. P.S.I. 400#. S.I.P. 200#.
Hooked up to backside - pumped 30 sxs cement. Max. P.S.I. 300#.
Blew hole in 8 5/8" in cellar.

Perfs:

Top	Bot	Thru	Comments
3428	3444		
3406	3410		

INVOICED

DATE 12-22-08
INV. NO. 2009060889

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 20 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

Signed

(TECHNICIAN)

CM

PKT

