

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-10028-00-00  
Spot: SESWSW Sec/Twnshp/Rge: 5-30S-8W  
330 feet from S Section Line, 990 feet from W Section Line  
Lease Name: POMEROY J G Well #: 2  
County: KINGMAN Total Vertical Depth: 4290 feet

Operator License No.: 31337  
Op Name: WILDCAT OIL & GAS LLC  
Address: 10286 SW 170TH AVE  
NASHVILLE, KS 67112

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP	4.5	4120		
PROD	4.5	4288	1540	
SURF	8.625	303		

139.43

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/28/2008 10:30 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND BOTTOM BACK TO 3790' AND CAP WITH 4 SKS CMT. REC CASING. SPOT 35 SKSW 1300', 35 SKSW 850' CIRC 350-0'

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/28/2008 11:30 AM KCC Agent: STEVE VANGIESON

**Actual Plugging Report:**

THE PERFS WERE COVERED WITH SAND TO 3790', AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 1540', AND PULLED TO 1300', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 850', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 350', WHERE CMT WAS CIRCD TO SURFACE.

**Perfs:**

Top	Bot	Thru	Comments
4220	4225		
3844	3849		

INVOICED

DATE 12-22-08  
INV. NO. 2009060891


RECEIVED  
KANSAS CORPORATION COMMISSION  
**NOV 26 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: QUALITY OIL WELL CEMENTING. 60/40 4% GEL

Plugged through: CSG

District: 02

Signed \_\_\_\_\_



(TECHNICIAN)

PKT