

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-20418-00-00
Spot: NWSE Sec/Twnshp/Rge: 29-32S-12W
1980 feet from S Section Line, 1980 feet from E Section Line
Lease Name: THOMAS/FORSYTH Well #: 5
County: BARBER Total Vertical Depth: 4455 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-------------------------------|
| PROD | 4.5 | 4453 | 0 | WITH 100 SX CMT |
| SURF | 8.625 | 214 | | WITH 225 SX CMT <u>144.79</u> |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/04/2008 3:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: CIBP @ 4350' & 4 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 245' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/04/2008 5:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

CASING LEAKS @ 3100' & FROM 300'-600'. HAD NO STRETCH IN 4 1/2" CASING . CUT OFF 8 5/8" SURFACE PIPE TO GET SLIPS OUT OF BRADEN HEAD. FOUND CMT IN BRADEN HEAD & APP. 1' BELOW TOP OF SURFACE PIPE. APPARENTLY CASING LEAKS @ 300'-600' SQUEEZED WITH CMT BY PREVIOUS OPERATOR. NO CMT RECORDS SANDED BACK TO 4350' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. WAIT ON 600' OF 2 3/8" TBG TO BE DELIVERED. RAN 2 3/8" TBG INTO 600' CIRCULATED CMT TO SURFACE WITH 50 SX CMT. LAID DOWN TBG. TIE ONTO 4 1/2" CASING WITH SWEDGE. PUMPED 45 MORE SX OF CMT @ 50#. SHUT IN. 11/6/08: TOPPED 4 1/2" CASING OFF WITH 45 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4412 | 4416 | | |
| 4408 | 4438 | | |

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 24 2008
CONSERVATION DIVISION
WICHITA, KS


INVOICED

DATE 12-22-08
INV. NO. 2009060892

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: TBG

District: 01



Signed Stephen J. Puffer
(TECHNICIAN)