

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-20646-00-00
Spot: N2NWNW Sec/Twnshp/Rge: 33-32S-12W
4950 feet from S Section Line, 4620 feet from E Section Line
Lease Name: TEDROW Well #: 5
County: BARBER Total Vertical Depth: 4565 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4563	2610	WITH 75 SX CMT
SURF	.8.625	235		WITH 175 SX CMT <u>148.36</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/17/2008 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK TO 4450' & 4 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 260' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/17/2008 12:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SAND BACK TO 4450' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT WITH 50# HULLS. 2ND PLUG AT 260' WITH 50 SX CMT WITH 50# HULLS. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4512	4522		


INVOICED
DATE 12-22-08
INV. NO. 2009060892

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 24 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL 3%CC BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)