

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-27438-00-00

Spot: NWSWSESW

Sec/Twnshp/Rge: 25-23S-14E

605 feet from S Section Line, 1485 feet from W Section Line

Lease Name: HURST

Well #: 4

County: WOODSON

Total Vertical Depth: 1308 feet

Operator License No.: 8210

Op Name: BIRK, EDWARD E.

Address: 302 S 16TH ST
BURLINGTON, KS 66839

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	40	0	

42.51

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/18/2008 3:00 PM

Plug Co. License No.: 8210

Plug Co. Name: BIRK, EDWARD E.

Proposal Rcvd. from: LAURA BIRK

Company: EDWARD E. BIRK

Phone: (620) 364-2745

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASD BORE TO 1308'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT 1308', A 50' CEMENT PLUG AT 700', AND A CONTINUOUS CEMENT PLUG FROM 200' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL

WitnessType: NONE

Date/Time Plugging Completed: 11/18/2008 5:00 PM

KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

DRILL PIPE WAS RAN INTO THE WELL TO 1308'. THE WELL WAS GELLED FOR BRIDGING PURPOSES. 10 SACKS OF CEMENT WERE PUMPED THROGH THE DRILL PIPE TO 1308'. THE DRILL PIPE WAS PULLED TO 700' AND 10 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE DRILL PIPE WAS PULLED TO 200'. CEMENT WAS PUMPED INTO THE DRILL PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE DRILL PIPE WAS REMOVED. DILPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED
KCC DISTRICT #3

NOV 26 2008 CPT

CHANUTE, KS

INVOICED

DATE 12-23-08

INV. NO. 2009060897

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 03 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: DP

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)